

BOULT
CUMMINGS
CONNERS
& BERRY
PLC

Henry Walker
(615) 252-2363
Fax: (615) 252-6363
Email: hwalker@bccb.com

LAW OFFICES
414 UNION STREET, SUITE 1600
POST OFFICE BOX 198062
NASHVILLE, TENNESSEE 37219

November 20, 2000

TELEPHONE (615) 244-2582
FACSIMILE (615) 252-2380
INTERNET WEB <http://www.bccb.com/>

Mr. David Waddell
Executive Secretary
Tennessee Regulatory Authority
460 James Robertson Parkway
Nashville, TN 37243-0505


In Re: *Generic Docket to Establish UNE Prices for Lines Sharing per FCC 99-355, and
Riser Cable and Terminating Wire as Ordered in TRA Docket 98-00123.*
Docket No. 00-00544

Dear David:

Please find enclosed the original and thirteen copies of the Rebuttal Testimony of Dean R. Fassett filed on behalf of the Data Coalition in the above-captioned proceeding. Please bring this to the attention of Director Lynn Greer, the Hearing Officer in this proceeding.

BOULT, CUMMINGS, CONNERS & BERRY, PLC

By:


Henry Walker

HW/nl
Attachment
c: Parties

**BEFORE THE TENNESSEE REGULATORY AUTHORITY
NASHVILLE, TENNESSEE**

In re:)
Generic Docket To Establish UNE Prices)
for Line Sharing Per FCC 99-355, and) Docket No. 00-00544
Riser Cable and Terminating Wire as)
Ordered in Authority Docket 98-00123)

**REBUTTAL TESTIMONY
OF
DEAN R. FASSETT
ON BEHALF OF
THE DATA COALITION ***

PUBLIC VERSION

NOVEMBER 20, 2000

*** DIECA Communications, Inc. d/b/a Covad Communications Company,
Broadslate Networks of Tennessee, Inc. and MGC Communications, Inc. d/b/a
Mpower Communications are jointly filing this testimony as the Data Coalition.**

INDEX

	<u>PAGE</u>
I. Introduction	3
A. Summary	3
B. Purpose	8
II. xDSL Capable Loops	8
A. Engineering Assumptions That Must Underlie Forward-Looking ILEC Costs	8
B. The Authority Should Reject BellSouth's Revised Dispatch Rate Assumption for Voice-Grade Loops	13
C. Facilities Used for xDSL Capable Loops are Identical or Nearly Identical to Those Used for Voice Grade Loops	15
D. Necessary Steps for Provisioning a Stand Alone xDSL Capable Loop	20
E. BellSouth Dramatically Increases the Cost of Provisioning XDSL Loops by Including Unreasonable Task Times, Unnecessary Work Groups, and Invalid Assumptions In its Cost Studies	26
Task Group 1 – Service Inquiry	29
Task Group 2- Engineering	35
Task Group 3 – Connect & Turn-Up Test	36
III. Line Sharing	43
IV. Loop Conditioning	50
V. Loop Qualification	75

1
2
3 **I. INTRODUCTION**

4 **Q. PLEASE STATE YOUR NAME AND BUSINESS ADDRESS.**

5 A. My name is Dean R. Fassett and my business address is 141 Juniper Drive,
6 Ballston Spa, New York, 12020.

7 **Q. BY WHOM AND IN WHAT CAPACITY ARE YOU EMPLOYED?**

8 A. I am the owner of Adirondack Telcom Associates. Currently, I am providing
9 telecommunications consulting services concerning outside plant infrastructure
10 design, construction and engineering issues relating to the provisioning of xDSL
11 in Tennessee to DIECA Communications, Inc. d/b/a Covad Communications
12 Company, Broadslate Networks of Tennessee, Inc. and MGC Communications,
13 Inc. d/b/a Mpower Communication, who I understand are filing testimony jointly
14 in this proceeding as the "Data Coalition."

15 **Q. ON WHOSE BEHALF ARE YOU TESTIFYING?**

16 A. I am testifying on behalf of the Data Coalition.

17 **Q. PLEASE SUMMARIZE YOUR BACKGROUND IN OUTSIDE PLANT**
18 **ENGINEERING AND CONSTRUCTION.**

19 A. I have over 30 years of telecommunications experience in outside plant
20 engineering and construction. Prior to my retirement from NYNEX in May 1996,
21 I had outside plant engineering and construction responsibilities for the
22 Adirondack District as the Area Operations Manager. This work included both
23

1 the actual performance of outside plant engineering work and the supervision of
2 construction personnel performing those tasks. Before that assignment, I was the
3 Engineering Manager for the Capital South District. In this capacity, I was
4 responsible for all engineering operations for the design and construction of the
5 local network within an area that encompassed metropolitan, suburban and rural
6 environments. During these assignments I personally participated in and was
7 responsible for numerous projects that included:

- 8 • The planning/design and construction of a \$10.7 million 117 mile interoffice
9 SONET project
- 10 • Design and deployment of numerous fiber fed DLC systems within 69 central
11 offices
- 12 • Design and construction of feeder and distribution facilities to meet the
13 service requirements for a customer base of approximately 400,000 residential
14 customers
- 15 • OSP rehabilitation projects to upgrade distribution plant to engineering design
16 standards for the 69 central offices under my responsibility
- 17 • Designing and provisioning of numerous digital services to meet the
18 requirements of business customers within city and rural environments
19 including the first HDSL application within region and first PG Flex
20 installation within NYNEX
- 21 • Implementation and conversion and utilization of OSP assignment records to
22 mechanized databases
- 23 • Preparation and administration of contracts with vendors and labor contractors

1 Since my retirement from NYNEX, I have continued to work in the outside plant
2 engineering and construction arena working as a contract engineer and operations
3 manager on various projects. In summary, I have had a wide range of hands-on
4 experience that includes urban, suburban and rural network construction. From
5 late 1998 and until recently I was responsible for company operations and
6 engineering at Frontier Communications of AuSable Valley in upstate New York,
7 a small ILEC that until recently was an independent company. In that capacity, I
8 was responsible for the planning, engineering design and construction of all OSP
9 projects, including coordination with other utilities and service providers,
10 preparation and awarding of outside contracts and acquisition of material and test
11 equipment.

12
13 Thus, I have experience with both large and small ILECs. My Curriculum Vitae
14 is included as Exhibit DRF-1 to this testimony.

15
16 **Q. HAVE YOU RECEIVED ANY TRAINING IN OUTSIDE PLANT**
17 **ENGINEERING AND CONSTRUCTION?**

18
19 **A.** Yes. I have attended many outside plant training courses for engineering and
20 construction at the Bell System and Bellcore Training Centers including, among
21 others, Principles of Digital Technology, Applied Transmission, Advanced
22 Distribution Design, Underground Conduit Systems, SONET, FACS, COSMOS-
23 RCMAC/engineering, Engineering Economy, Loop Technology Planning, along

1 with private training available through various vendors including Nortel, NEC,
2 Alcatel, 3M, and Siecor.

3 **Q. HAVE YOU TESTIFIED BEFORE OTHER PUBLIC UTILITY**
4 **COMMISSIONS?**

5 A. Yes. Since 1996, I have testified before several State Public Service
6 Commissions. Exhibit DRF-1 also identifies the various proceedings in which I
7 have participated.

8
9 **Q. HOW IS YOUR REBUTTAL TESTIMONY ORGANIZED?**

10 A. Following this introductory section, my testimony is organized in the following
11 fashion:

- 12 • Section II summarizes of the purpose of my testimony, including a brief
13 explanation of outside plant engineering, which relates to the provisioning of
14 xDSL loops and responds to issues raised in BellSouth's cost studies and
15 testimony filed in this docket.
- 16 • Section III responds to BellSouth's proposal that xDSL loops be priced
17 substantially higher than voice grade loops, by explaining xDSL technologies
18 and deployment and by illustrating that, from an engineering perspective,
19 xDSL services utilize the same loop facilities that ILECs use to provide voice
20 grade services;

- 1 • Section IV responds to BellSouth's excessive nonrecurring charge for Line
2 Sharing.
- 3 • Section V discusses line conditioning ("Loop Modification" as BellSouth calls
4 it) and explains why the pricing both Bell South and United Telephone-
5 Southeast ("Sprint") propose for loop conditioning is unreasonable;.
- 6 • Section V responds to the loop qualification rate proposals sponsored by
7 BellSouth and Sprint.

8 **Q. PLEASE SUMMARIZE THE CONCLUSIONS IN YOUR TESTIMONY?**

9 A: My testimony is based upon proper implementation of sound engineering design
10 guidelines for creating and constructing a network that is forward looking. In
11 contrast, the network shown in BellSouth's cost studies is not forward looking.
12 Moreover, its cost studies are contaminated with flawed assumptions and grossly
13 inflated costs for the provisioning of xDSL services. BellSouth has falsely
14 assumed that provisioning xDSL capable loops is substantially different from
15 provisioning basic loops used to provide POTS or voice grade service and thus
16 require special design. This is simply not the case. BellSouth also
17 inappropriately assumes that extensive manual intervention will be required to
18 provision xDSL capable loops, while existing and forward looking electronic
19 database systems actually eliminate such extensive manual activity. These
20 flawed assumptions and the grossly overstated costs increase costs and discourage
21 meaningful competition. In this testimony I will demonstrate why the work times,

costs proposed by BellSouth are unjustified, and I propose reasonable task times and engineering design assumptions upon which this Authority can rely.

Q. WHAT IS THE PURPOSE OF YOUR REBUTTAL TESTIMONY?

A. The Data Coalition asked that I address the direct testimony and cost studies presented by Bell South Telecommunications, Inc. and United Telephone – Southeast, Inc. (“Sprint”) in this proceeding. In addition, I will provide technical support for economic cost witness Michael Starkey and information for the Authority concerning the establishment of UNE prices for line sharing. I will respond to BellSouth’s proposals on loop conditioning, loop qualification and other issues pertaining to the provisioning of voice and advance services that will be crucial in the creation of a truly competitive marketplace, which will benefit consumers in Tennessee.

II. XDSL CAPABLE LOOPS

A. ENGINEERING ASSUMPTIONS THAT MUST UNDERLIE FORWARD LOOKING ILEC COSTS

Q. WHAT IS THE DEFINITION OF THE ACRONYMS “DSL” AND “xDSL”?

A. The acronym “DSL” means digital subscriber line and the “x” in “xDSL, is a variable, meant to encompass the various types of digital subscriber line technologies and is used when referring generally to DSL. Digital subscriber line technologies are transmission technologies used on circuits that run between a customer’s premises and the central office.

1 **Q. IN HIS DESCRIPTION OF BELL SOUTH’S xDSL CAPABLE LOOP**
2 **PRODUCTS, DOES BELL SOUTH WITNESS MILNER SEEM TO LIMIT**
3 **XDSL LOOPS TO “ALL COPPER?”**

4 A. Yes. Although traditionally, DSL technologies have been deployed on loops that
5 are copper end-to-end from the central office to the customer premises (“home
6 run copper”), the current deployment of fiber fed NGDLC systems by ILECs
7 enables some forms of DSL to be provisioned using hybrid loops, consisting of
8 fiber and copper. On those hybrid loops, DSL services are provisioned on copper
9 cable pairs from the customer’s premises to a mid-point equipment location,
10 known as a Remote Terminal (“RT”), where signals are combined and transmitted
11 over fiber transmission systems from the RT to the central office (“fiber-fed
12 loops”).

13 **Q. WHAT KEY ENGINEERING DESIGN GUIDELINES MUST THE**
14 **AUTHORITY CONSIDER TO SET COST-BASED RATES FOR XDSL**
15 **ELEMENTS IN TENNESSEE?**

16 A. I will provide a brief background of fundamental engineering principles, which
17 should underlie the ILEC’s, proposals in this case. My criticisms of BellSouth’s
18 engineering assumptions are grounded in these engineering guidelines.

19 **Q. PLEASE BRIEFLY DESCRIBE THE ENGINEERING DESIGN**
20 **GUIDELINES THAT OUTSIDE PLANT ENGINEERS HAVE**

1 **FOLLOWED TO DESIGN LOCAL NETWORKS AND HOW HAVE**
2 **THESE GUIDELINES EVOLVED?**

3 A. During the early 1960's until approximately 1972, outside plant design guidelines
4 mandated the use of a Feeder Distribution Interface ("FDI"). The FDI provided a
5 manual cross-connection and demarcation point between feeder and distribution
6 plant. Compared to "multiplied plant" (designed for party-line service via
7 multiplied bridged taps) which had a single cable pair appear for assignment in
8 several locations, interfaced plant provides greater flexibility in the network. In
9 the early 1970's, the Serving Area Concept ("SAC") design was introduced as a
10 prescription simplified engineering planning and design method, and was the first
11 major attempt to modernize the network for providing ubiquitous and expanded
12 service to an ever shifting customer base.

13 Under SAC design, the distribution cable network is connected to the feeder
14 network at a single interconnection point, the serving area interface (or Feeder
15 Distribution Interface, "FDI") with no multiplied copper feeder cable facilities
16 (i.e., Zero bridged tap). In 1980, the SAC design concept was incorporated into
17 the Carrier Serving Area concept ("CSA").

1 **Q. DID THE INTRODUCTION OF THE CARRIER SERVING AREA**
2 **(“CSA”) DESIGN GUIDELINES AND USE OF DIGITAL LOOP**
3 **CARRIER SYSTEMS IN THE FEEDER SEGMENT OF THE LOCAL**
4 **NETWORK CHANGE THE ENGINEERING PLANNING PROCESS?**

5 A. Yes. Introduction of the Carrier Serving Area (“CSA”) design guidelines and
6 utilization of DLC in the feeder portion of the local network changed the
7 engineering planning process. This design change was implemented in 1980. A
8 “CSA” is a planning entity consisting of a distinct geographic area that can be
9 served by a single Digital Loop Carrier (“DLC”) Remote Terminal (“RT”) site.
10 The geographic area could encompass a single Distribution Area (“DA”) or
11 multiple DA’s. The maximum allowable bridge-tap rule was relaxed from no
12 bridged tap under SAC guidelines to 2.5 kft, with no single bridged-tap longer
13 than 2.0 kft. Also, all CSA loops must be unloaded and should not consist of
14 more than two gauges of cable. As BellSouth Witness Milner acknowledges at
15 page 4, the CSA design rules provided economic benefits to the ILECs as well as
16 requiring that the ILECs outside plant be developed to support both broadband
17 (i.e. DSL) and narrowband (i.e., voice) technologies.

18 **Q. HAS THE EXTENSIVE DEPLOYMENT OF FIBER IN THE FEEDER**
19 **SEGMENT OF THE NETWORK AND DEPLOYMENT OF NGDLC**
20 **SYSTEMS IMPACTED THE LOCAL NETWORK?**

1 A. Yes, as fiber fed digital loop carrier systems have become the preferred method of
2 providing feeder facilities and fiber has been deployed more extensively into the
3 network, the utilization of copper feeder facilities is diminishing. This has
4 enabled ILEC's, including BellSouth, to construct a network that is capable of
5 providing voice and advanced services much more efficiently for customers
6 distant for a central office than older copper feeder networks, while greatly
7 reducing expenses and improving service quality. This has also enabled
8 consumers that previously were unable to enjoy the benefits of xDSL services and
9 other advanced services to be able to receive the same advanced services as
10 customers located near the central office.

11 **Q. WERE ENGINEERING GUIDELINES MODIFIED OR REVISED AS THE**
12 **DEPLOYMENT OF FIBER FED DLC SYSTEMS BECAME MORE**
13 **ECONOMICAL?**

14 A. Yes, as the economical benefits of deploying fiber fed digital loop carrier were
15 being realized and costs continued to decrease, many engineering guidelines and
16 network planning strategies were revised or changed. In 1983, the
17 recommendation to implement Revised Resistance Design (RRD) was distributed
18 to all Bell Operating Companies. These revised resistance design rules stated that
19 in essence, loops 18 kft. or less (total length including bridged tap) must be
20 designed to 1300 Ohms or less and must be non-loaded; that loops greater than 24
21 kft. should be designed using DLC, that bridged tap was limited to 6 kft.
22 maximum, and that no loaded bridge tap, and no bridge tap between loads, was

1 permitted. *See Exchange Area Transmission-Revised Resistance Design,*
2 *BellSouth's Response to Covad's First Request for Production.*

3 As BellSouth Witness Milner admits on page 5, the economic break point for
4 deploying fiber fed DLC has continued to gravitate closer to the central office and
5 most ILECs have established guidelines that indicate fiber fed digital loop carrier
6 should be utilized for loops greater than 9 to 12 kft. from the central office.
7 Some ILECs have even established closer break points. In his testimony
8 BellSouth witness Milner indicates an economic crossover point for using fiber
9 fed NGDLC of 12,000 feet. These changes eliminated the requirement for load
10 coils in the local network and any existing load coils should be removed as digital
11 loop carrier replaces physical copper facilities.

12 **B. THE AUTHORITY SHOULD REJECT BELLSOUTH'S**
13 **REVISED DISPATCH RATE ASSUMPTION FOR VOICE-**
14 **GRADE LOOPS**

15 **Q. IN ITS REVISED NONRECURRING COST FILING, BELLSOUTH HAS**
16 **INCREASED ITS DISPATCH RATE ASSUMPTION FOR SL-1 VOICE-**
17 **GRADE LOOPS FROM 20% to 38%. IS THIS INCREASE**
18 **APPROPRIATE?**

19 **A.** No. As Mr. Starkey explains in his testimony, it is not appropriate to include any
20 level of fieldwork costs in the non-recurring charge for a SL-1 loop. However,
21 even if the Authority were to accept that some fieldwork costs should be included
22 in the non-recurring charge, it should reject BST's assumed dispatch rate
23 increase.

1 **Q. WHY SHOULD THE AUTHORITY REJECT BST'S DISPATCH RATE**
2 **ASSUMPTION?**

3 A. A dispatch rate of 38% is simply too high. It has been long understood that
4 dispatching of technicians is very costly and ILECs should avoid doing so if
5 possible. Outside plant facilities have been designed under "Cut-Through" design
6 to avoid the need for field dispatches to lay in a simple cross connection at the
7 Serving Area Interface ("SAI"), and have pre-connected more than one pair of
8 drop wire conductors at the Drop Terminal and the Network Interface Device
9 ("NID"). Internally, local exchange carriers typically measure their success in
10 avoiding field dispatches via a performance measure referred to as the "NPV" rate
11 (*i.e.*, "No Premises Visit"). To operate efficiently successful operations normally
12 operate at an NPV rate between 85% and 90% (which corresponds to a dispatch
13 rate of 10% to 15%). Improvements in outside plant engineering design and
14 operating practices have been steadily lowering the need for the actual dispatch of
15 a technician. BellSouth's original rate of 20% was too high. Therefore, instead
16 of increasing that rate, BST's forward-looking analysis should show decreasing
17 dispatch rates.

18 BellSouth has filed no evidence or supporting material that would allow
19 me to analyze how it arrived at its higher 38% conclusion. Indeed, BST has not
20 even supported its original dispatch rate assumption of 20%. Mr. James R.
21 McCracken, one of BST's subject matter experts for the Installation &
22 Maintenance ("I&M") and Special Services Installation & Maintenance
23 ("SSI&M") work groups, admitted that he doesn't know the source of the

1 dispatch percentages and further that he doesn't have any experience with SL-1
2 loop installation. [See Deposition of James R. McCracken, July 28, 2000, Tr. at
3 81-83.]

4 For all of these reasons, if the Authority decides to allow any nonrecurring
5 dispatch charge, BST's original estimate of a 20% dispatch rate is a much more
6 reasonable, and even a generous, proxy for field visits than its revised,
7 unsupported estimate of 38%.

8 **Q. DO THESE DESIGN GUIDELINES HAVE AN impact ON THE COSTS**
9 **AND RATES BELL SOUTH PROPOSES FOR VARIOUS XDSL UNES**
10 **AND RELATED SERVICES.**

11 A. Yes. I will explain their impact on BellSouth's cost proposals in the xDSL loop
12 section, the line sharing section, the conditioning section, and loop makeup
13 section.

14 C. **FACILITIES USED FOR XDSL CAPABLE LOOPS ARE**
15 **IDENTICAL OR NEARLY IDENTICAL TO THOSE USED**
16 **FOR VOICE GRADE LOOPS**

17 **Q. DO BELL SOUTH'S COST STUDIES GIVE THE IMPRESSION THAT**
18 **XDSL CAPABLE LOOPS ARE COMPLICATED TO PROVISION?**

1 A. Yes. BellSouth's cost studies, with the myriad of xDSL capable loops and the
2 enormous nonrecurring charges for those loops, create the impression that DSL
3 providers are asking BellSouth to perform extraordinary tasks when they order an
4 xDSL capable loop. This is reflected in the special "design process" BellSouth
5 requires for xDSL capable loops and in the task times, work groups, and
6 assumptions upon which BellSouth's cost studies rest.

7 **Q. HOW DO XDSL-CAPABLE LOOPS DIFFER FROM VOICE-GRADE**
8 **LOOPS?**

9 A. The facilities used to provide xDSL services are identical or nearly identical to
10 those used to provide voice-grade services in forward looking local networks. In
11 fact, for loops that would be provisioned entirely on copper facilities given
12 current engineering practices, xDSL-capable loops are identical to loops used to
13 provide voice-grade service. BST witness Milner acknowledged as much at page
14 13 of his direct testimony:

15 Significantly, the same copper loops that are used to provide DSL
16 services are also utilized to provide voice service to BellSouth's
17 customers, as well as to other CLECs' customers.
18

19 **Q. IF VOICE SERVICE IS BEING PROVIDED OVER FIBER FED DLC**
20 **FACILITIES, CAN XDSL SERVICE STILL BE PROVISIONED OVER**
21 **THE SAME LOOP LIKE THOSE LOOPS ON ALL COPPER**
22 **FACILITIES?**

1 A. Yes. If the incumbents have built their existing loop plant to comply with
2 decades-old design standards, all-copper loops under 18,000 feet in length should
3 be xDSL-capable today. The maximum copper loop length included in an
4 analysis based on forward-looking, efficient engineering practices would be
5 18,000 feet. As I discussed earlier in my testimony and BST witness Milner
6 confirms, the economic crossover point between the use of copper feeder versus
7 fiber feeder and Digital Loop Carrier (“DLC”) systems is generally a loop length
8 substantially below 18,000 feet. Thus, copper loops shorter than this length will
9 support xDSL technology without any adjustments whatsoever, provided they are
10 free of interferors like load coils and excessive bridged tap.

11 With this network architecture, as with all-copper loops, the copper
12 distribution portion of the loop is identical whether the service provided is basic
13 voice-grade analog service or an xDSL-based service. Likewise, incumbents can
14 provision both basic exchange voice grade services and xDSL-based services
15 using the same NGDLC systems and the same fiber feeder facilities. Forward-
16 looking DLC equipment incorporates the DSLAM/splitter function into line cards
17 that are placed in the remote terminal (RT). In this forward-looking configuration
18 with DSL-compatible DLCs, the copper sub-feeder pair will terminate on a line
19 card with integrated DSLAM/splitter functionality that plugs into one of the
20 channel banks in the DLC equipment located in the ILEC’s RT. Simply stated in
21 this DLC configuration the line sharing functionality has been shifted from the
22 central office to the remote terminal location. From the remote terminal fiber
23 feeder facilities transmit both the voice and data components of the loop back to

1 the incumbent's serving central office where the data traffic is then routed to the
2 CLECs collocation facilities. Depending upon the type NGDLC system deployed,
3 this transmission can occur over the same fiber or on separate fibers. Basically the
4 only difference between provisioning xDSL service over copper based facilities
5 and fiber fed NGDLC is that some of the functionality performed at the central
6 office is now performed at the remote terminal. As a result, customers on long
7 loops who were once restricted from DSL service can enjoy the benefits of DSL
8 service.

9 **Q. CAN INCUMBENTS PHYSICALLY PROVISION XDSL-CAPABLE**
10 **LOOPS OVER THE SAME EXISTING FACILITIES THAT THEY USE**
11 **TO PROVISION VOICE-GRADE LOOPS TODAY?**

12 A. Yes. If the ILECs in Tennessee have been building and maintaining their
13 networks in a manner that meets engineering standards that have been in place for
14 decades as discussed earlier in my testimony, they can provision xDSL-capable
15 loops over the same facilities used to provision voice-grade loops, in most cases.
16 In fact, in his testimony BST witness Milner describes BellSouth's developing
17 network as one that would be enable BellSouth to provide xDSL capable loop
18 over the same facilities as voice service is being provided. For all-copper loops up
19 to 18,000 feet in length, competitors providing xDSL services need nothing more
20 than a basic loop free of impediments such as load coils, excessive bridged tap,
21 repeaters, Digital Added Main Lines ("DAMLs"), noise, or any other condition
22 that has a deleterious effect on xDSL-based services.

1 **Q. HOW DO WE KNOW THAT XDSL LOOPS ARE THE SAME AS VOICE**
2 **GRADE LOOPS?**

3 A. We know this for several reasons. First, DSL was initially developed to expand
4 the economic usefulness of then existing, ubiquitous telephony infrastructure.
5 Delivering high-speed data on that existing telephone network saved the ILECs
6 the time and expense of deploying a new and duplicative network for delivering
7 such services. Therefore, DSL, from the very beginning, was designed to ride on
8 the existing telephone outside plant network. Second, the use of Line Sharing by
9 ILECs and by competitors proves that all competitors need for DSL is a simple
10 voice grade loop. Line Sharing proves that a single facility may one day support
11 only voice service, then the next day can be used for voice and data, and then the
12 day after that can be used for data only. The actual facility never changes and,
13 thus, the pricing of DSL loops should reflect this fact.

14 **Q. YOU HAVE JUST SHOWN THAT XDSL SERVICES ARE (BY DESIGN)**
15 **INTENDED TO BE PROVISIONED OVER THE SAME BASIC LOOPS**
16 **AND NETWORK ARCHITECTURE THAT THE ILECS HAVE**
17 **DEPLOYED FOR YEARS (AND CONTINUE TO DEPLOY). ARE THE**
18 **ILEC COST STUDIES SUBMITTED IN THIS PROCEEDING**
19 **CONSISTENT WITH THAT FACT?**

20 A. No, not at all. BellSouth's cost studies submitted in this docket grossly distort the
21 nature and requirements of xDSL service providers.

22 **Q. HOW HAS BELL SOUTH DONE THIS?**

1 A. Several ways. BST begins by artificially defining and limiting its xDSL
2 capable offerings, through proposing a series of f loop types and loop
3 transmission standards that it would impose on xDSL loops. (Milner at p.
4 10-12). Then, BellSouth requires all xDSL capable loops to be
5 provisioned through a cumbersome “design process,” which imposes
6 numerous special processing steps on delivery of these loops. In turn, all
7 of these unnecessary steps, work groups, and assumptions increase the
8 cost of provisioning a simple xDSL capable loop. None of these steps are
9 useful or desirable for xDSL providers such as the Data Coalition. For
10 example, BellSouth has an engineer design in a test point on every DSL
11 circuit. That process breaks the normal, inexpensive, flow-through
12 provisioning of the loops and, in turn, leads to additional recurring and
13 nonrecurring costs to wire in that testing facility. These and other related
14 costs are entirely unnecessary and do nothing but harm to the competitive
15 market for xDSL services in Tennessee.

16 D. NECESSARY STEPS FOR PROVISIONING XDSL
17 LOOPS
18

19 Q. IF THE AUTHORITY REJECTS BST’S INAPPROPRIATE “DESIGNED
20 LOOP” ASSUMPTIONS FOR XDSL, WHAT ACTIVITIES AND TASK
21 TIMES SHOULD BE INCLUDED IN A NONRECURRING COST STUDY?

22 A. Costs for access to loop makeup information and/or “conditioning,” that may or
23 may not be necessary for any specific loop, if determined to be appropriate at all
24 by this Authority, should be recovered as part of a charge specific to those

1 activities. Therefore, the only activities relevant to processing an order to connect
2 an individual loop are: 1) processing and reviewing a CLEC service order; 2)
3 placing the required jumper to connect the loop appearance in the central office to
4 the (prewired) collocation cross-connection; and 3) completing or closing out the
5 work in OSS. Because these are the same steps required for a basic unbundled
6 loop, there is no reason why the nonrecurring work times or costs for all-copper
7 xDSL loops should be different than for a basic, non-designed loop. However,
8 because of the overstatement of appropriate work times used in BST's cost studies
9 in docket 97-01262, the Authority should make the adjustments I have indicated
10 to determine the cost of xDSL unbundled loops.

11 **Q. IN YOUR OPINION WHAT IS A REASONABLE TIME ESTIMATE TO**
12 **PROCESS AND REVIEW A CLEC SERVICE ORDER REQUEST?**

13 A. I would estimate on average that it would take no more than 2 to 2 1/2 minutes to
14 pull and analyze a work order to connect an xDSL-capable loop. Typically
15 technicians retrieve a printout of all assigned orders that are generated
16 automatically and perform the necessary cross connect or "jumper" work during
17 specific times of the day. Furthermore, orders are accessed from mechanized
18 systems where a technician pulls up more than one order at a time. Generally, the
19 technician will then organize the orders so that they can be efficiently performed.
20 Once the technician gets the orders, most orders would only require negligible
21 review and are a routine work task for experienced technicians. An order that
22 requires running a jumper is a routine task for a central office frame technician.

1 Technicians are very familiar with the locations of the “to” and “from” points on
2 the frame within their assigned central offices and can efficiently place the
3 required cross connections without delay.

4 **Q. WHAT IS A REASONABLE TIME TO PLACE A CROSS CONNECTION?**

5 A. The placement of a cross connection to connect the loop to collocation should
6 only take a few minutes, even considering walking time. Since experienced
7 technicians know the frame very well and the process of attaching a cross
8 connection to the frame is very routine and almost automatic. In some locations
9 with non-staffed central offices, the technician would need to travel to an office
10 location to perform the specific cross connection work. Therefore, some travel
11 time may also be required in order to complete this task. However this travel time
12 should be minimal on a per-line basis if the ILEC is efficiently utilizing their
13 workforce. First, most lines will be located in staffed offices. Second, when
14 work in a non-staffed office is required, it can typically be coordinated with other
15 work to complete the necessary tasks efficiently. Travel time would only be
16 assigned to each loop with a 5% occurrence based on the assumption that 80% of
17 loops are in staffed locations and four loops are grouped into a batch (on average)
18 before a technician is dispatched. Based on the further assumption that a non-
19 staffed office is typically 20 minutes from a dispatch location, then each loop
20 would only be assigned one minute of travel time. In my opinion and based upon
21 my personal experiences, I believe these are reasonable assumptions.

1 **Q. WHAT IS INVOLVED IN CLOSING AN ORDER AND HOW LONG**
2 **SHOULD THAT TASK TAKE ORDER?**

3 A. In closing an order the technician is simply noting into a automated system that
4 the requested work has been completed. This task should take less time than it
5 took to originally “pull” and analyze because no analysis whatsoever is required.
6 Typically an efficient technician will perform this work task in a batch mode once
7 numerous assigned cross connections have been placed. On average, I would
8 estimate that it should take about 1.5 minutes to report work complete for each
9 line on an order.

10 **Q. IS THERE ANY ADDITIONAL COST IN PROCESSING AN ORDER**
11 **ITSELF?**

12 A. Any additional cost in processing an order would only applied in very limited
13 cases. The OSS used by ILECs’ are fully capable of managing the flow of a basic
14 order, which should include the cross connection of a loop regardless of the
15 intended use for that loop, in a fully automated mode. Manual task time required
16 to process an order for an unbundled loop would only be required in a very small
17 percentage of cases in which the mechanized OSS cannot identify facilities and
18 assign the work correctly. Since an ILEC should have adequate up-front edits in
19 place and have maintained accurate database records, the percentage of such
20 fallout should be very low. In my opinion, I would estimate that this percent
21 fallout should be around 2% in an analysis of efficient, forward-looking costs. On

1 average this it might take about 15 minutes to review, analyze and resolve such
2 problems. Given this assumption the correction of errors in the ordering process
3 would legitimately take an additional 0.3 minutes on a per-line basis.

4 **Q. IN DISCONNECTING AN XDSL-CAPABLE LOOP IS THE WORK**
5 **ACTIVITY REQUIRED APPROXIMATELY THE SAME AS THE TIME**
6 **YOU JUST REVIEWED FOR CONNECTING THE LOOP?**

7 A. Yes. However the actual cross connection work associated with removing or
8 disconnecting would take less time simply because it is quicker to pull a jumper
9 off of a frame connection than to make a new connection.

10 **Q. PLEASE SUMMARIZE THE STEPS AND TIMES THAT SHOULD BE**
11 **INCLUDED IN THE NONRECURRING COST TO CONNECT AN**
12 **ORDERED BASIC OR XDSL-CAPABLE LOOP.**

13 A. The following tables provide a reasonable estimate of the tasks and work times
14 required to provision a basic copper loop (for use to provide basic exchange
15 analog service or an xDSL service).

Tasks, Times and Costs Required to Efficiently Connect an Unbundled Loop			
Task	Minutes	Occurrence	Minutes per Line
Obtain and Review Order	2.5	100%	2.5
Travel to Remote Office	20	5%	1
Place Jumper	3	100%	3
Report Work Complete	1.5	100%	1.5
Total Minutes Per Line			8
Estimated (Proxy) Labor Rate			\$ 40.00
Total Cost			\$ 5.33

1 As the preceding table indicates, if one assumes for the sake of illustration that
2 this Authority adopts a forward-looking average labor rate of about \$40 for the
3 related work groups for any given ILEC, then the total cost to connect an
4 unbundled xDSL loop should be about \$5.33. The price should be about \$5.33
5 plus any adopted common cost markup. As shown in the following table, the
6 costs and rates for disconnect would be very similar.

Tasks, Times and Costs Required to Efficiently Disconnect an Unbundled Loop			
Task	Minutes	Occurrence	Minutes per Line
Obtain and Review Order	2.5	100%	2.5
Travel to Remote Office	20	5%	1
Remove Jumper	2	100%	2
Report Work Complete	1.5	100%	1.5
Total Minutes Per Line			7
Estimated (Proxy) Labor Rate			\$ 40.00
Total Cost			\$ 4.67

1 Since the process of placing and removing cross connections in central
2 offices is very consistent with most ILECs and with only minor variations
3 due to labor rates, I would anticipate that the results in the preceding tables
4 would not vary across ILECs.

5 **E. BELLSOUTH DRAMATICALLY INCREASES THE**
6 **COST OF PROVISIONING XDSL LOOPS BY INCLUDING**
7 **UNREASONABLE TASK TIMES, UNNECESSARY WORK**
8 **GROUPS, AND INVALID ASSUMPTIONS IN ITS COST**
9 **STUDIES**
10

1 **Q. Should the Authority rely upon the BST analysis of the nonrecurring**
2 **cost to provision various types of unbundled loops for use to provide**
3 **xDSL services?**

4 A. No. I have reviewed the BellSouth cost studies of October 2, 2000, October 20,
5 2000 and November 13, 2000, with respect to their support of the BellSouth
6 proposed rates for UCL, ADSL, and HDSL loops in Tennessee. (See BellSouth
7 Ruscilli Testimony, Ex. JAR-1). Since the revised cost studies filed on November
8 13, 2000 altered several aspects of xDSL loop provisioning, I am continuing to
9 review those studies and to contrast them to the October 2, 2000 BellSouth study.

10 Even though I've only had a short time to review the new BST study, it is
11 clear that BST's analysis is simply irrelevant to the work effort that would
12 reasonably be required to provision the xDSL-capable unbundled loops that the
13 Data Coalition needs. After having reviewed the numerous BST cost studies and
14 supporting materials that have been presented in this proceeding, I am still unclear
15 about what BST perceives it was analyzing. xDSL loops, particularly those
16 provided over all-copper facilities, are exactly like basic, voice grade loops.
17 Therefore, as I will explain below, the connection of a xDSL loop should involve
18 only a few basic tasks that are required in order to connect a copper loop to a
19 collocation facility in the central office. In its cost studies, BST has included
20 numerous irrelevant tasks. Moreover, even if these tasks were somehow relevant,
21 BST's study includes activities that even a moderately efficient ILEC would have
22 mechanized and task times that are entirely overstated.

1 **Q. WHAT ACTIVITIES DOES BST INCLUDE THAT ARE ENTIRELY**
2 **IRRELEVANT TO THE PROVISION OF XDSL-CAPABLE LOOPS?**

3 A. BellSouth has created an elaborate “designed loop” process and it requires that all
4 xDSL loops it provisions go through this process. From an engineering
5 perspective, this entire design process is unnecessary. Significantly, the designed
6 loop process triggers involvement of unnecessary work groups, the inclusion of an
7 unnecessary “test point” on the DSL loops, and generates a Design Layout Record
8 and Order Coordination functions that were not requested and are not required by
9 DSL providers. In the following section of my testimony, I will identify some of
10 the extreme examples of grossly inflated task times or unnecessary activities
11 found in BellSouth’s cost studies for xDSL capable loops.

12 **Q. If the Authority inappropriately agrees with BST’s approach of designing**
13 **each individual xDSL loop, based on its definitions of those loops, could the**
14 **Authority rely on the BST reported costs without substantial adjustment?**

15 A. No. As I have noted above, even if this Authority agrees with BST that it must
16 hand design and test each xDSL unbundled loop (using unnecessary manual
17 processes at each step), BST has grossly overstated the cost of each step. Until
18 BST identifies the basis for many of its cost study assumptions, I cannot identify
19 each and every instance of where BST’s nonrecurring cost study shows
20 unnecessary, unsupported or inflated task times. The examples based on BST’s

1 xDSL Loop studies set forth below clearly illustrate that BST's nonrecurring cost
2 analysis is substantially flawed and should not be relied upon in this proceeding.

3 **Q. HOW HAVE YOU REVIEWED AND ANALYZED BELL SOUTH'S TASK**
4 **TIMES AND WORK GROUPS FROM THE XDSL STUDIES?**

5 A. In its various cost studies on xDSL loops, BellSouth places various work groups
6 and task times into three general categories: Service Inquiry, Engineering and
7 Connect & Test. As I discuss below, none of these groups are necessary to
8 provision a DSL loop. Nonetheless, I will describe the work activities or
9 assumptions made in BellSouth's cost study and explain why those activities and
10 assumptions are unnecessary and invalid. Where the task is necessary to
11 provision xDSL capable loops, I have suggested reasonable task times based on
12 efficient practices. I will address them in the general categories used in the
13 BellSouth studies for simplicity sake.

14 **TASK GROUP 1: SERVICE INQUIRY**

15 Although BellSouth seems to have eliminated some of these unnecessary Service
16 Inquiry function when the CLEC performs its own loop qualification (and thus
17 orders a loop without loop makeup), many unnecessary, manual processes remain
18 when a CLEC orders loop with loop makeup. It is critical that the Authority
19 adjust rates for both loops with and loops without loop makeup for two reasons.
20 First, at the time of this filing, no CLECs in Tennessee can obtain loop makeup
21 electronically in advance of ordering a loop. Although BellSouth is beta testing

1 this electronic process, the reality is that CLECs today must order a loop with
2 loop makeup or else obtain a separate manual loop makeup in advance of ordering
3 the loop. One of the Data Coalition Members, Mpower, is currently forced to
4 endure this process that adds 5-7 business days to the front end of the ordering
5 process at a cost of \$233 per inquiry. Thus, although BellSouth purports to have
6 both loops with and loops without loop makeup available, the only real choice for
7 CLECs is to obtain manual loop makeup from BellSouth. As a result, the task
8 times BellSouth assigns to these processes must be carefully analyzed.

9 BST assumes that, on 33% of orders, two different groups (the Complex
10 Resale Services Group (“CRSG”) and the Local Carrier Services Center
11 (“LCSC”)) will require 1.58 hours, (95 minutes) hours of “Service Inquiry” work
12 to manually determine if an xDSL-qualified loop is available. A forward-looking
13 analysis should instead assume that the CLEC has access to the ILECs OSS that
14 includes the necessary data to qualify its own loops. Therefore, all of the tasks
15 elaborated in BellSouth’s cost study for Service Inquiry functions are
16 unnecessary. This is true regardless of whether a CLEC orders an xDSL loop
17 with or without loop makeup. The order should be submitted electronically to the
18 ILEC, and should flow through to provisioning without manual intervention. For
19 these reasons these costs should be entirely removed from any analysis that is
20 premised on considering forward looking costs.

21 If the Authority does not simply eliminate these costs, the Authority will
22 need to adjust these costs substantially. BST provides no explanation of the

1 functions of the Complex Resale Group (CRSG) and the Local Carrier Serving
2 Center ("LCSC") (the two work groups performing Service Inquiry functions,
3 according to the BellSouth cost studies) in its direct testimony or cost studies.
4 Nonetheless, the Data Coalition has been able to piece together some explanation
5 of what these groups do from discovery, testimony and hearing transcripts in
6 Florida and North Carolina pricing proceedings.

7 BST assigns to the CRSG nearly an hour of labor (50 minutes) for tasks
8 like receiving a firm order SI from a CLEC and screens documents; CRSG
9 prepares/sends transmittals to OSPE for verification of facility availability. Upon
10 completion of job, CRSG informs CLEC facilities are available. This effort
11 appears to consist entirely of reviewing the CLEC request and translating it into a
12 different format that another work group uses and, ultimately, sending notice back
13 to the CLEC when the Service Inquiry is done. Those are functions that a
14 mechanized OSS does automatically and should not be portrayed as an necessary
15 component in forward looking cost studies.

16 The next process step is that the LCSC "receives SI from CRSG, validates
17 for accuracy and sends a firm order commitment BST reports that this manual
18 process requires another 45 minutes. I have been unable to find any work papers
19 supplied by BST that even basically identifies specifically how the 45-minute
20 estimate was developed. However, a document produced by BellSouth in Florida
21 states, "Manual work times for the LCSC ... 1st install ... 30 (15 min to screen &

1 15 min to process order).”¹ Based on that discovery, it appears that BST began by
2 overstating its input by 50%. More importantly, this step appears to be entirely
3 busy-work created by BST's own manual transcription of a CLEC's request. In
4 other words, the CRSG does nothing more than checking the work of the first
5 group, all before the work gets to the actual group that performs the provisioning.
6 Having a single work group that manually checks orders for errors seems
7 inefficient, but having two separate groups checking for errors is ludicrous. More
8 importantly, this work should all be done electronically with little or no manual
9 intervention.

10 The work tasks for the two remaining work groups that perform Service
11 Inquiry functions, Outside Plant Engineering (“OSPE”) and Service Advocacy
12 Center (“SAC”) are equally mysterious. BellSouth proposes a total of 113
13 minutes of engineering time on each loop. In the Florida proceeding, BellSouth
14 proposed 180 minutes for the same tasks. During that proceeding, the Outside
15 Plant Engineering subject matter expert, Michael K. Zitzmann, who supplied the
16 task times for the OSPE and SAC group portions of the Service Inquiry was
17 deposed. In that deposition, Mr. Zitzmann revealed that his 180-minute estimated
18 task time for those groups consists of 30 minutes for clerical processing and
19 updating of BST's plant records, plus 150 minutes for a BST engineer to look up
20 the facility records for the requested loop route. (Exhibit DRF-2, Zitzmann
21 Depo., p. 44) Given the unexplained changes to the BellSouth cost studies, it is
22 impossible to say which of these task times decreased. Nonetheless, these

¹ See BellSouth's Response to Rhythms' Request for Production of Documents No. 3.

1 enormous task times means that Mr. Zitzmann has assumed that a BST engineer,
2 working with plant records for a central office with which he is familiar, with full
3 access to all of BST's mechanized plant records for that office and with the paper
4 records for that office at hand, can trace only three or four loops per day. This
5 assumption is totally unrealistic based on my experience as an OSP engineer with
6 extensive experience. Because he was not able to provide a detailed breakdown
7 of how he arrived at his estimates, it is not possible to analyze exactly how Mr.
8 Zitzmann went wrong. His deposition does, however, provide some clues. For
9 example, Mr. Zitzmann is only marginally familiar with BST's mechanized plant
10 databases such as LFACS because he acknowledges that 13 years ago "... when I
11 was an engineer, LFACS was brand new." (Exhibit DRF-2, Zitzmann Depo., p.
12 100) In fact, Mr. Zitzmann seems to have exaggerated the time required for even
13 the most basic uses of mechanized systems. For example, Mr. Zitzmann first
14 asserted that "[i]t takes longer than five minutes ..." just to log into LFACS.
15 (Exhibit DRF-2, Zitzmann Depo., p. 47) He later seemed to admit that the log-in
16 process involves only two screens and a few key strokes. (Exhibit DRF-2,
17 Zitzmann Depo., pp. 101-104)

18 Contrary to Mr. Zitzmann's exaggerated estimate, when BST has
19 complete records, a qualified engineer or even an experienced clerical assistant
20 would never need to leave his terminal to qualify loop facilities and might
21 complete the job in the matter of a few minutes. Furthermore, BellSouth Witness
22 Pate testified that some basic information exists electronically in the BellSouth
23 Loop Facilities Assignment and Control System ("LFACS") on all loops. (Pate

1 Direct, p. 7) That information includes loop length, whether the loop is fiber or
2 copper, the presence of Digital Loop Carrier ("DLC"), and whether it is loaded.
3 Furthermore, Mr. Pate stated that extensive and detailed information was
4 available in LFACS on 80% of loops in metropolitan areas, where most orders for
5 DSL are placed. (Pate Direct, p. 7) Thus, although BellSouth estimates that
6 manual loop makeup will be necessary 33 % of the time, it seems that the
7 necessary information will be available electronically much more often than that.
8 BST's assumption that manual loop makeup will be required 33% of the time is a
9 gross overstatement. Such an effort should only be required when mechanized
10 qualification fails, which should be less than 10 percent of the time.

11 In those cases in which the BST engineer find the information somewhere
12 other than LFACS, the process should still take less than an hour in a worst case
13 scenario. This has been confirmed by BellSouth witness Greer during the North
14 Carolina hearing. Greer admitted that he could produce a loop make-up pull from
15 BellSouth systems in 5-10 minutes. He also admitted that an experienced
16 engineer could probably do it much more quickly. As an overall average, I
17 believe an efficient BST operation could look up the required information and
18 forward it to a CLEC within 10 minutes, on average. When I was an outside plant
19 engineer and when I managed other engineers, I would certainly not have found it
20 acceptable for them to complete no more than 3 loop orders in a day.
21

TASK GROUP 2: ENGINEERING

The second cluster of tasks in the BST analysis is for “engineering.” The first engineering task is for the Circuit Provisioning Group (“CPG”) work group, which apparently processes requests, designs circuit, and generates DLR & WORD document for CLEC and Field. This task appears to consist of two distinct time estimates for correcting fallout in the automated engineering process at two different points, which take 15 and 18 minutes respectively. BST assumes that each type of fallout will occur on 15% of all orders. (BST’s response to Rhythms’ Request for Production of Documents 3 in Florida) BST’s work papers provide no clue as to how the fallout percentages in its study were developed. Hence, because BST failed to provide the source documents for either portion of its cost calculation formula, no detailed analysis is possible.

In addition to the “CPG” work, but also without support, BST assumes that the Assignment Facilities Information Group (“AFIG”) work group will spend 8 minutes to “assign loop facilities” as needed to correct fallout in the assignment process for an additional 30% of xDSL loops. Overall, BST is assuming that its automated processes will fail an amazing 55 % of the time on a cumulative basis in this engineering process.

1 As mentioned above, this entire engineering process is unnecessary. If this
2 Authority should wish to include it, the assumed breakdown rate of 55 % (in this
3 single, minor portion of the order process) is totally out of line with any
4 reasonable forward-looking OSS process. I would recommend that this Authority
5 only allow a very small percentage fallout occurrence across the entire
6 “engineering” activity (e.g., 1 percent each for the BST’s three types of fallout
7 would be conservative). This adjustment to the occurrence factor for
8 “engineering” tasks would help to compensate for any overstatement in task times
9 that BST advocates.

10 **TASK GROUP 3: CONNECT & TURN-UP TEST**

11 Under the label “Connect & Turn-up Test” in its cost study BST includes work by
12 a number of distinct groups, each of which I will address separately below.

13 UNE Center Group

14 BST reports 255.11 minutes for work by the “UNE Center.” BST describes this
15 function as “UNEC pulls info, assigns to work forces; verifies & ensures accuracy
16 of design; creates cut sheets to verify reuse of facilities; ensures dispatch,
17 performs frame continuity and due date coordination and testing; performs
18 manual order coordination (RCF, disconnect and UL order) when service is
19 converted on existing facilities, task times, which BST failed to explain or
20 support.) and contacts customer and completes order.” Based on the July 20,

1 2000 deposition of Mr. James Franklin Ennis, the BST expert who provided the
2 UNE Center inputs, it appears that the basic role of the UNE Center is to
3 coordinate and perform remote testing on design loops such as BST “ADSL
4 Loop.” (Exhibit DRF-3, Ennis Depo., pp. 11-14) As noted above, I do not
5 believe that it is necessary or appropriate for an xDSL-capable loop to be
6 designed and specially wired to allow the ILEC remote test access. Without such
7 design steps and extra wiring, no remote testing would even be possible, and the
8 UNE Center work would be eliminated.

9 Even if this Authority were to improperly adopt a designed xDSL Loop
10 assumption, the UNE Center cost for testing those loops is greatly overstated.
11 For example, the UNE Center time includes functions such as “ensures dispatch”
12 meaning that a UNE Center employee literally checks to make sure that BST’s
13 automated systems did not fail to schedule the dispatch of a field technician to
14 coordinate the testing process with the UNE Center. (Exhibit DRF-3, Ennis
15 Depo., p. 21) This is obviously unnecessary and should be removed from a
16 forward-looking cost study.

17 The most extreme is that BST’s study appears to assume that this
18 workgroup will spend a total of 54 minutes to test continuity. A continuity test is
19 one of the most routine, simple and rapid activities in central office operations. If
20 required at all, it is typically done at the same time a connection is made and
21 involves little more than clipping standard test apparatus onto the newly
22 completed connection. This task should take substantially less than one minute
23 and should only be done once at most. BST’s reported task time is more than 50

1 times too high. In my opinion, conservatively an additional five minutes would
2 be adequate for the work activity for an efficient equivalent of the UNE Center
3 testing process.

4
5 There are numerous other task which account for the excessive time
6 attributed to the UNE Center, which further exacerbate the lack of efficiency in
7 that process. For example, BST includes manual work time to “pull” the order, to
8 “assign to work force,” to “ensure accuracy of design,” to “ensure dispatch.”
9 Forward looking Operation Support Systems (OSS) used by efficient ILECs have
10 automated all of these activities and should not require any standard manual
11 intervention. BST apparently has mechanized at least some of these tasks but,
12 ironically, has built in a 100% manual backup to make sure, for example, that the
13 automated dispatch that should have been scheduled automatically was actually
14 scheduled. One can only assume that BST is intentionally causing fallout (*i.e.*, a
15 need for manual intervention and additional labor costs) for those activities
16 simply because a competitor for xDSL service will use the ordered loop. Also,
17 BST includes both time to manually contact customer and to manually “complete
18 order,” two tasks that should accomplish the same objective. BST’s analysis is
19 saturated with such duplicative and unnecessary manual activities, which even a
20 moderately efficient ILEC would have fully mechanized or automated for their
21 retail operations. BellSouth certainly has done so and has those systems available
22 and these manual task are totally unnecessary in most instances.

It is not surprising that BST's estimates are so far off. Although Mr. Ennis was the subject matter expert on which BST relied to support the UNE Center cost estimates, he did not actually develop those estimates. Instead, he merely agreed to accept the cost estimates provided to him by the cost group. He had no idea from where the estimates used actually came or how they were developed. (DRF-3, Ennis Depo., pp. 50-52)

“WMC” Work Group

BST reports 15 minutes for the “WMC” group to “coordinate dispatched technicians.” BST failed to provide a word of explanation regarding how this time was developed or what exactly is supposed to take place for the reported 15 minutes. BST’s alleged need for yet another layer of manual coordination is contrary to efficient engineering practices using forward-looking OSS. The Authority should not allow any recovery for this group and activity until BST provides compelling justification concerning why it is necessary.

CO I&M

BST includes 20 minutes for 85% of loops for the Central Office Installation & Maintenance (“CO I&M”) group to “wire circuit at collocation site.” Based on the July 20, 2000 deposition of Mr. Daniel Eric Stinson (the BellSouth subject matter expert on CO I&M), it appears that this is based on an assumed ten minutes to review the order and walk to the frame location, and five minutes to run each of two frame jumpers one on the main distribution frame and another to connect a BST remote test head (thereby making the loop “designed”). (Exhibit DRF-4, Stinson Depo., pp. 29-30) Other than the assumption that a

1 second jumper is required to include a designed test point, I agree that the basic
2 functions for this work group are required. However, I do not agree with the BST
3 time estimates and have presented my own recommended alternative times for
4 those functions earlier in this section of my testimony. If and only if the
5 Authority approves BST's recommendation to design in a test point, I recommend
6 that this task should take a total of 11 minutes.

7 For example, BST reports that the "pull info" task requires 8 minutes.
8 This task should not require any manual time at all, as information required for
9 work on an assigned order is typically either printed or loaded into a queue in a
10 work terminal automatically in a mechanized OSS environment. Even if, for
11 some odd reason, a manual lookup were required, it should not take anything near
12 8 minutes merely to retrieve the information needed to process an order.

13 The 85% assumption appears to be based on a BST note that the study
14 "... assume[s] 15% of total are carried in other transport elements." This is not
15 explained and does not make any obvious sense. Indeed, Mr. Stinson seemed
16 unclear as to where or how the remaining 15% of the CO I&M costs might be
17 captured. (Exhibit DRF-4, Stinson Depo., p. 24) Therefore, I recommend
18 increasing the occurrence of this work from 85% to 100% when applying the
19 occurrence to my more reasonable time estimates.

20 Outside Plant or Field Work

21 Finally, BST assumes 194 minutes of outside plant or fieldwork plus 20
22 minutes of travel time for *every* xDSL loop order. This work should not be

1 included in a forward-looking analysis of nonrecurring costs because it is already
2 captured in the recurring cost analysis.

3 Not only is this cost entirely double counted, BST's analysis again
4 overstates task times. xDSL loops will not require a dispatch in 100% of cases
5 under any reasonable set of assumptions. As a forward-looking assumption, the
6 Commission should not assume that an xDSL loop will require a dispatch of
7 outside plant technicians any more often than is required for a basic loop, which
8 BST assumes will be required for only 20% of basic unbundled loops.

9
10 BST's 194 minute total task time estimates include:

- 11 1) 16 minutes for "Actual placement and/or removal of cross
12 connection jumpers, performance of line and station transfer work,
13 or bearing of connect through."
- 14 2) 15 minutes to "Check loop pair(s) for continuity, and/or dial tone
15 before leaving cross connect box, LST, PXJ, RXJ, BCT location."
- 16 3) 20 minutes for "Time spent 'hooking up' test equipment and
17 performing operational test from the network interface."
- 18 4) 19 minutes for "Technician closes out service order on CAT
19 and/or on phone with the ICM."
- 20 5) 45 minutes for an "Attempt to resolve problems with continuity of
21 the loop or lack of dial tone" on 30% of all lines.
- 22 6) 56 minutes of "Time spent in trouble resolution following failure
23 test performed at the network interface" on 21% of all loops.

1 All of the preceding detail comes from Exhibit DDC-1 Caldwell Direct
2 Testimony 11-13-00 in this proceeding.

3 Each of these estimates greatly exaggerates the time required, on average,
4 for a qualified technician to perform the required task. Some of the individual
5 tasks, in the sequence from items 1 through 4 above, such as item 1, can be
6 accomplished in a minute or less. Considering the entire series of tasks in
7 sequence (including setup time), I estimate that it might take an average of 25
8 minutes in total.

9 Likewise, the cumulative *** **BST PROPRIETARY** [REDACTED] **END**
10 **PROPRIETARY** *** presumed error rate reflected in items 5 and 6 is totally
11 inconsistent with the performance level one would expect from an efficient
12 service provider with a forward looking designed network. BST has provided no
13 support whatsoever for its assumptions and therefore has failed to prove that they
14 form the reasonable basis for a forward looking rate. I recommend allowing BST
15 to include only a maximum of a 5% occurrence for each type of error.

16 **Q. PLEASE SUMMARIZE THE FINDINGS YOU HAVE JUST PRESENTED.**

17 A. The following table compares the BST reported times by function with the times I
18 consider to be more appropriate for either a forward-looking cost study of a basic
19 loop, including an xDSL loop, or a realistic study of a designed loop process.

1

Group or Function	BST Assumed Time	Realistic Time Assumption W/O Design Process	Realistic Time W/ Engineered/Design Process
Group 1: Service Inquiry	95 Minutes on 80% of orders	"0" Minutes (Should be mechanized and is part of another element)	10 Minutes on 10% of orders
Group 2: Engineering	8 Minutes on 30% of orders 15 Minutes on 15% of orders 18 Minutes on 15% of orders 87 Minutes of 10% of orders	"0" Minutes (xDSL loops should not be designed)	8 Minutes on 1% of Orders 15 Minutes on 1% of Orders 18 Minutes on 1% of Orders
Group 3: CONNECT & TEST (UNEC)	255 Minutes for multiple tasks at various occurrences	"0" Minutes (Remote testing is not required on non-designed loop)	5 Minutes additional time for test at the MDF at time of installation
Group 3: CONNECT & TEST (WMC)	15 Minutes per loop	"0" Minutes - Not required	"0" Minutes - Not required - No explanation provided by BST
Group 3: CONNECT & TEST (CO I & M)	20 Minutes on 85% of loops	8 Minutes on 100% of loops	11 Minutes on 100% of loops
Group 3: CONNECT & TEST (SSI&M)	194 Minutes for multiple tasks at various occurrences	"0" (recurring cost in a forward looking study)	50 Minutes total for 20% of loops (includes 5% additional error correction time)
Approximate Cost	\$ \$ 186.23	\$5.33	\$ 18.27

2

3

III: LINE SHARING

4

Q. CAN "DSL" SERVICE BE PROVIDED OVER A CUSTOMERS

5

EXISTING POTS SERVICE FACILITY?

6

A. Yes, DSL services can be provided over existing telephone lines with a

7

technology known as line sharing or line splitting. As BellSouth Witness

1 Milner's testimony illustrates, CLECs are now entitled to purchase only the high
2 frequency spectrum of the local loop for DSL services, if they wish.

3 **Q. WAS BELLSOUTH WITNESS MILNER'S DESCRIPTION OF HOW**
4 **LINE SHARING WORKS FAIRLY ACCURATE?**

5 A. Yes, basically. In the telecommunications industry, the use of a single loop that is
6 capable of providing both POTS and certain high-bandwidth xDSL digital
7 transmission capabilities between a customer's premises and the central office is
8 possible. This is because voice traffic occupies a narrow bandwidth in the lower
9 end of the spectrum available on a loop, traditionally accepted in the industry to
10 be between 300 and 3400 Hz. For those types of xDSL services that permit line
11 sharing, xDSL traffic occupies the high end of the spectrum available on a loop
12 (i.e., Above 4000 Hz). Therefore, both low-bandwidth POTS and high-
13 bandwidth xDSL can coexist on a single physical loop.

14 **Q. WHAT TYPES OF xDSL CAN BE PROVIDED IN A LINE SHARING OR**
15 **LINE SPLITTING ARRANGEMENT?**

16 A. Since POTS over a copper loop normally occupies the frequencies between 300
17 and 3400 Hz, an Asymmetric Digital Subscriber Line, (ADSL) can be provisioned
18 on the same loop. This is because both the downstream and upstream data signals,
19 which are transmitted on different frequencies, use frequencies above the range of
20 frequencies used to transmit voice signals. ADSL uses the bandwidth above the
21 4-kHz POTS frequency to transmit duplex data using digital modulation

1 techniques. It was originally developed to support the delivery of entertainment
2 video, or “video dial tone,” services over existing copper loops. Such video
3 services require much higher bandwidth in the “downstream” direction (towards
4 the customer premises) than they do in the “upstream” direction (towards the
5 central office). This is because the video signals being transmitted to the
6 customer’s premises require a large amount of bandwidth, and the upstream signal
7 is assumed to be a non-video data signal requiring much less bandwidth. Thus,
8 the need for bandwidth was deemed to be asymmetrical; that is, a high-bandwidth
9 signal exists in the downstream direction and a lower bandwidth signal exists in
10 the upstream direction. ADSL is also useful for consumer Internet access,
11 because such traffic tends to display an asymmetrical pattern similar to video dial
12 tone services. Most Internet traffic flows toward the end user, as graphics-
13 intensive web pages and data files are downloaded. The upstream traffic
14 normally consists of a few keystrokes and occasional uploads of email and small
15 data files.

16 RADSL, (Rate Adaptive Digital Subscriber Line) a type of ADSL, can also be
17 used in a line sharing arrangement. Just like ADSL, the downstream and
18 upstream data signals are transmitted using separate frequencies and both data
19 streams use frequencies above the frequencies used to transmit voice signals.
20 Therefore, RADSL can be used on the same loop as POTS service in a line
21 sharing arrangement. As is the case with other types of ADSL, the downstream
22 and upstream data transmission rates are asymmetrical (as an alternative, it is also
23 possible to configure RADSL for symmetrical data transmission rates). RADSL

1 is more flexible than other types of ADSL because it is rate adaptive; that is, the
2 DSL equipment automatically and dynamically adjusts the transmission speed of
3 the circuit to the optimal level achievable on each loop. RADSL can therefore
4 transmit data at a wide range of transmission speeds, depending on the length and
5 condition of the loop in question.

6 G.Lite is a throughput limited version of ADSL, used on loops with simple filters,
7 rather than splitters, at the subscriber end. G.Lite eliminates the requirement for a
8 splitter installation at the customer premise. It uses the same part of the frequency
9 spectrum as ADSL, and thus can be used in a line sharing arrangement.

10 Additional enhancements and modifications to xDSL will surely continue in this
11 technology aggressive industry.

12 **Q. BELLSOUTH WITNESS MILNER'S TESTIMONY SEEMS TO LIMIT**
13 **THE USE OF LINE SHARING TO PROVISIONING ADSL. IS THAT**
14 **ACCURATE?**

15 A. Not entirely. In addition to ADSL, some other variations of DSL service include
16 SDSL, HDSL, VDSL and IDSL. These are all symmetrical configurations of
17 xDSL where the downstream and upstream data signals are transmitted using a
18 full range of frequencies, including those used to transmit voice signals. While
19 most symmetrical DSL services currently can not provide voice and data service
20 over the same facility, some technological advances will surely change that
21 limitation in the very near future. In fact in the September 2000 issue of
22 TELECONNECT, there is an article discussing North Pittsburgh Telephone

1 Company's deployment of Xpres-DSL service, which uses a symmetric form of
2 DSL, called MVL (Multiple Virtual Line) that unlike standard SDSL, shares the
3 line with voice.

4 **Q. DOES EITHER BELL SOUTH OR SPRINT ATTRIBUTE ANY COST TO**
5 **THE HIGH FREQUENCY SPECTRUM OF THE LOOP?**

6 A. No. Both ILECs agree that there is no cost associated with providing just the high
7 frequency spectrum. At page 6 of his direct testimony, Sprint witness Gordon
8 states:

9 Sprint believes if an ILEC customer currently subscribes to voice, then
10 the ILEC recovers its loop cost through the retail rate of the service, access
11 charges and any subsidies that the ILEC might receive. Also in its cost
12 study documentation filed in this docket Sprint states:

13 No incremental loop costs are created in the use of the high frequency
14 portion of the loop via a line sharing arrangement. Accordingly, Sprint's
15 Interstate xDSL retail offering cost study included no local loop cost
16 allocation

17 BellSouth likewise agreed that the cost of the high frequency spectrum of
18 the loop is zero.

19 **Q. HAS BELL SOUTH PROPOSED REASONABLE NONRECURRING**
20 **CHARGES FOR INSTALLING A SPLITTER.**

21 A. No. BellSouth seeks to impose a charge \$371.63 on CLECs when they
22 order either 24 or 96 ports on a splitter. This cost appears to be related to

1 work inventorying circuit assignments. First, it makes no sense that a
2 CLEC would have to pay the same amount irrespective of whether it
3 orders 24 or 96 ports. Second, the work times for these activities are
4 grossly exaggerated. BellSouth proposes that it should take 4.0 hours for
5 its network group and 4.41 hours for the engineering group to do this
6 routine work. The network aspect of this function is merely a matter of
7 building the pertinent information into a standard database that, if
8 programmed correctly, should take no more than 30 minutes for 96 ports
9 and even less for a 24 port splitter. The engineering associated with this
10 work task as well is considerably overstated and should only require 30
11 minutes at most and essentially is not required at all. BellSouth has not
12 provided any supportable documentation for these proposed charges.

13
14 However, as Mr. Starkey states in his testimony, any cost
15 associated should have been capitalized and non-recurring costs are
16 unwarranted.

17 **Q. HAS BELL SOUTH PROVIDED ANY JUSTIFICATION FOR**
18 **THESE CHARGES?**

19 A. No. As I previously stated, BellSouth has not provided any justification
20 for their proposed non-recurring charges for installing a splitter.

21 **Q. ARE BELL SOUTH'S PROPOSED WORK ACTIVITIES AND**
22 **TASK TIMES FOR PROVISIONING A LINE SHARED LINE**
23 **REASONABLE?**

1 A. No. The BellSouth line sharing proposal suffers from many of the same
2 problems the xDSL loop nonrecurring studies suffer from. Namely,
3 manual intervention where a forward looking OSS should be in place,
4 manual review of existing electronic processes, and excessive time for
5 work tasks. With line sharing, the only work that need to be done
6 whatsoever to provision a loop, is removing one jumper and running two
7 other jumpers. The Data Coalition's witness Zulevic explains this process
8 in more detail. The Data Coalition's witness Starkey explains how
9 BellSouth has calculated the costs for line sharing inappropriately and
10 suggests the reasonable way to price this UNE.

11 **Q. WHAT AMOUNT OF TIME DOES BELL SOUTH ESTIMATE IT**
12 **WILL TAKE TO PROVISION A LINE SHARED LOOP?**

13 A. In response to Covad's First Interrogatories No. 28, BellSouth stated that
14 depending upon the frame configuration, the time required to place
15 jumpers to provision a line shared loop would vary between 21 and 36
16 minutes, depending on the network architecture in place in a BellSouth
17 office. Of course, BellSouth provides no information about how often a
18 certain network configuration exists. Nonetheless, as I have said earlier in
19 my testimony, running jumpers is the only task necessary for provisioning
20 a line shared loop. The placement of these cross connections or jumpers
21 should not take a qualified, experienced, technician very long and
22 certainly not the excessive times that BellSouth is proposing. In my

1 opinion, conservatively this work operation may take a technician on
2 average 11 minutes.
3

4 **IV. LOOP CONDITIONING**

5 **Q. FOR THE PURPOSE OF THESE PROCEEDINGS, PLEASE DEFINE THE**
6 **TERM XDSL LOOP CONDITIONING.**

7 A. Loop Conditioning refers to the removal of impediments on the copper loop to
8 permit the functionality of xDSL transmission. This includes the removal of all
9 load coils, excessive bridged tap, repeaters, range extenders, and low pass filters.

10
11 **Q. DO BELLSOUTH PROPOSED LOOP CONDITIONING CHARGES**
12 **REFLECT THE EVOLUTION OF OUTSIDE PLANT DESIGN**
13 **GUIDELINES USED THROUGHOUT THE INDUSTRY FOR THE PAST**
14 **SEVERAL DECADES?**

15 A. No. As discussed earlier in my testimony, under established industry Outside
16 Plant engineering planning and design guidelines all copper loops since 1980
17 should have been designed in concert with CSA concepts, which support digital
18 services. All loops since 1972 should have been, at a minimum, designed to
19 Serving Area Concept criteria, in which all distribution cables within the entire
20 Distribution Area have the same transmission characteristics (i.e., all loaded or all
21 non-loaded), the same copper cable gauge, and no excessive bridged taps.

22
23 In short, correctly designed Outside Plant for the past two decades should not
24 present any impediment to xDSL service loops requested by CLECs. Loops older

1 than 20 years are far beyond their useful service and depreciation lives.

2 Moreover, as work was done in the outside plant over the past 20 years, outside
3 plant engineers should have insured that BellSouth's plant was brought up to
4 these guidelines.

5 **Q. WHY IS LOOP CONDITIONING NECESSARY FOR XDSL LOOPS AT**
6 **ALL?**

7 A. CLECs must have access to a loop in which any copper segment is free of
8 impediments such as load coils, excessive bridged tap, repeaters, Digital Added
9 Main Line ("DAML"), noise, or any other condition that harms xDSL service.
10 The use of impairing devices in the network such as load coils and the allowance
11 of bridged taps longer than 2500 feet have been obsolete for the past 20 to 30
12 years, and should have been eliminated throughout the course of the outside
13 plant's life. Repeater and other old local loop devices either render local loops
14 unusable for even POTS service, or are so obsolete that they should have been
15 removed by ILECs when their use was no longer necessary. DAMLs are placed
16 as a temporary expedient on loops to mitigate a lack of outside plant facilities, and
17 should be removed by ILECs when they are no longer required due to the
18 provision of adequate facilities inventories. Impairing devices and technologies
19 would not exist on a loop designed to current standards, and they preclude or
20 degrade xDSL signals. However, such devices or conditions may exist in the
21 legacy-embedded plant, especially on older outside plant that has exceeded its
22 useful service life or has been rearranged for other uses than it was originally
23 designed to serve. Where older facilities of this kind remain in service, the ILEC

1 should remove them, to bring loops up to current ISDN/xDSL-capable
2 transmission standards.

3 **Q. DOES BELLSOUTH WITNESS MILNER ADEQUATELY EXPLAIN**
4 **WHAT LOAD COILS ARE?**

5 A. Basically. However, he fails to mention that load coils severely attenuate
6 frequencies above 3000 Hz, which is detrimental to both DSL loops and analog
7 data modems. Load coils are completely unnecessary on any loop less than
8 18,000 feet in length.

9 **Q. DO SUCH DEVICES INTERFERE WITH ANY EXISTING SERVICES**
10 **TODAY?**

11 A. Yes, and this harm is quite distinct from the fact that such devices interfere with
12 xDSL service. As the Authority is aware, the most common complaint of an
13 Internet user using a modem over a traditional POTS line is that although the
14 modem is capable of 56Kbps, that speed is almost never reached while surfing the
15 Internet and downloading files. Many of these complaints result from the presence
16 of this obsolete equipment (such as load coils) that should have been removed by
17 now, and is causing analog modem users to experience slower modem speeds..

18
19 Load coils significantly deteriorate the performance of analog modems on POTS
20 loops to as low as 21.6 kbps for a 56 kbps modem². Load coils also add

² Poor analog modem performance was the primary reason the FCC determined that any forward looking model used to determine loop costs for the purposes of its Universal Service Fund

unnecessary resistance to the loop³ thereby reducing the sound volume on the circuit. Severe degradation of modem performance is more important, in that analog modems designed for 56 kbps service use complex combinations of audio tones that require the full use of voice spectrum up to 3400 Hertz. Load coils block higher frequencies, thereby causing 56 kbps analog modems to self adjust themselves to much lower speeds, such as 21.6 kbps, based on the load coil reduced frequency spectrum available.

Q. WHAT ARE SOME OTHER REASONS WHY THE PRESENCE OF LOAD COILS ON LOOPS LESS THAN 18,000 FEET CAN ADVERSELY AFFECT VOICE-GRADE SERVICES?

A. The presence of load coils on loops less than 18,000 feet greatly increases the possibility of loading rules being violated and adversely impacting customer service. Loading rules include:

- Minimum sum of customer end section and bridge tap – 3,000 feet
- Loaded bridge tap – none permitted
- Bridge tap between loads – none permitted
- Stations (customers) between load points – none permitted

Q. SHOULD LOAD COILS EXIST ON COPPER LOOPS THAT ARE LESS THAN 18,000 FEET IN LENGTH?

proceedings should be based on loops free of load coils (See FCC May 7, 1997 Report and Order CC Docket No. 95-45 §250). The result was to increase the deployment of Digital Loop Carrier to avoid any analog copper loop being longer than 18,000 feet. The FCC did not address the preclusion of load coils on loops of less than 18,000 feet, because they recognize that load coils do not belong on such loops.

1 A. No. As I have previously stated, load coils on POTS loops were appropriate,
2 under old design guidelines, when copper loop lengths exceeded 18,000 feet. On
3 such long copper lengths, load coils serve to mitigate the build-up of capacitance.
4 However, according to engineering design rules that have been in place for 20
5 years or more, long loops, such as those over 18,000 feet, should be fed via
6 Digital Loop Carrier systems, so that load coils are never required. Any working
7 POTS loop less than 18,000 feet should have load coils removed to provide good
8 quality service. The presence of these devices on loops less than 18,000 feet are
9 detrimental to both POTS and advanced services.

10

11 **Q. DID BELLSOUTH WITNESS MILNER ADEQUATELY DESCRIBE**
12 **WHAT BRIDGED TAP IS?**

13 A. Yes, generally. Bridged tap is any section of a cable pair not on the direct
14 electrical path between the central office and end user. This condition increases
15 the electrical loss on the pair. It occurs when a cable pair has a three-way splice
16 (from the central office to location #1 to location #2), such that dial tone can
17 appear in two or more different cable pair locations. Visually, you can think of a
18 river with a stream entering it while the main branch of the river continues either
19 upstream or downstream. One fork continues necessarily to the customer premise
20 to complete the circuit. The second fork extends some distance into the field, but
21 never terminates at a end user.

³

At 8.5 ohms per load coil.

1 This approach to outside plant design became obsolete when party-line service
2 became largely obsolete. [See *Bellcore Notes on the Networks*, December 1997,
3 p. 12-3: "Multiple plant design [use of bridged tapped pairs] was largely replaced
4 by dedicated plant design because of the labor intensity of adding to or changing
5 existing plant and customer demands to convert from multiple-party line to
6 single-party line service.") Common in the days of party line service, bridged
7 taps should have been engineered out of the network since 1972. The high
8 frequency, digital nature of DSL services (like ISDN services) prevent them from
9 operating with more than 2,500 feet of bridged tap.

10 **Q. SHOULD BRIDGED TAP EVER APPEAR IN COPPER FEEDER PLANT?**

11 A. No. Bridged tap should not appear in copper feeder plant. Bridged tap in copper
12 feeder plant would exist if the same cable pair appeared as a feeder resource in
13 two different Serving Area Interfaces. However, such use of bridged tap is
14 inconsistent with Serving Area Concept ("SAC") guidelines, which have been in
15 use since 1972.

16 **Q. SHOULD BRIDGED TAP BE USED IN DISTRIBUTION PLANT?**

17 A. Although a backbone distribution cable may contain many cable pairs, once
18 distribution spans out into side legs, the same cable pair should never appear in
19 two different side legs. Distribution cable should always be engineered in 25-pair
20 binder groups, such that no pairs in a particular 25-pair binder group should ever
21 appear in more than one side leg. This ensures no bridged tap conditions between
22 separate distribution side legs.

1 **Q. SHOULD A LOOP MODIFICATION CHARGE BE IMPOSED BY ILECS**
2 **TO REMOVE INTERFERORS ON A COPPER LOOP?**

3 A. No. BellSouth should not be allowed to impose a Loop Modification charge, as it
4 is called, for loops less than 18,000 feet in length from either the central office or
5 remote DLC terminal. Those items that are classified as "Interferes" or
6 impediments should not occur on any copper loops properly designed over the
7 past 20 to 30 years. Moreover, as explained earlier, such impediments often
8 impair the quality of voice services.

9 **Q. WITNESS CALDWELL STATES THAT BELL SOUTH'S COST STUDY**
10 **USES COSTS THAT ARE FORWARD LOOKING AND REFLECT AN**
11 **EFFICIENT NETWORK DESIGN. PLEASE COMMENT.**

12 A. Contrary to Ms. Caldwell's statement the assumptions and costs used in
13 BellSouth's cost studies does not represent a "forward looking" efficient network
14 design. Even though Mr. Milner, describes what would be a forward looking
15 efficient network design in his testimony, BellSouth's cost study nevertheless
16 grossly differs from that methodology.

17 **Q. WOULD YOU PLEASE EXPLAIN?**

18 A. Yes. As I have discussed earlier in my testimony and BST witness Milner also
19 supports in his direct testimony, a forward looking network would be in
20 compliance with the engineering guidelines that have evolved over the decades. In
21 a forward looking efficiently designed network, loops greater than 18,000 feet
22 would be provisioned over fiber fed digital loop carrier and all loops would be
23 capable of provisioning advanced services. Therefore, the requirement to place

load coils or repeaters on long loops is eliminated and excessive bridge taps would not exist if BellSouth had adhered to those guidelines.

For example, BST's cost studies have inappropriately assumed a network that includes:

- load coils on an excessive number of loops, even those loops that are less than 18,000 feet from the central office
- loops less than 18,000 feet contain 2.1 load coils
- loops greater than 18,000 feet contain 3.5 load coils
- excessive bridge tap exists at 3 point on a loop and that even one of those bridge taps is in the underground feeder facilities

Q. IS THERE ANY EVIDENCE THAT THE CHARACTERISTICS OF LOOPS WITHIN THE NETWORK CHANGED AS THE SERVING AREA CONCEPT (SAC) AND CARRIER SERVING AREA CONCEPT (CSA) WERE IMPLEMENTED?

A. Yes. In Bellcore's "BOC Notes on the LEC Networks-1994", Issue 2, April 1994, the results of a survey indicate the implementation of SAC and CSA have impacted the characteristics of the local residential loop as follows:

Results of BOC Loop Surveys			
Year of Survey	1964	1973	1983
Average Working Length	10,613 ft	11,413 ft	11,723 ft
Average Total Bridge Tap	, 2478 ft	1,821 ft	1,490 ft

Q. PLEASE DESCRIBE HOW COPPER CABLES ARE CONSTRUCTED AND METHODS USED BY TECHNICIANS TO SPLICE CABLES.

1 A. Since the late 1960's, copper cables installed in the modern loop network
2 primarily have been plastic insulated copper conductor cable or "PIC" cable.
3 Plastic insulated conductor cable is designed for ease in cable pair identification.
4 It is made up of 25 pair, color-coded binder groups and is available in cable sizes
5 up to 4200 pair. Approximately 30 years ago, modular copper cable splicing was
6 introduced into the industry and remains the standard method of connecting or
7 splicing the network. With modular splicing, technicians can splice and rearrange
8 cable facilities very efficiently by the use of 25 pair splicing modules. These
9 splicing operations would also be applicable when load coils, bridge taps and
10 repeaters would need to be removed for loop conditioning. If permitted, I can
11 provide a brief demonstration of this splicing activity during the summary of my
12 testimony.

13 **Q. BST'S COST STUDIES ASSUME THAT ONLY 10 LOAD COILS WILL**
14 **BE REMOVED WHEN LOAD COILS ARE REMOVED FOR LOOP**
15 **CONDITIONING. IS THAT A REASONABLE ASSUMPTION?**

16 A. Not at all. First as I mentioned above BST should not be entitled to charge for the
17 removal of load coils on loops less than 18,000 feet, so BST's costs for loop
18 conditioning – short should be dismissed by this Authority. BST's assumption
19 that only 10 pairs would be unloaded at a time is totally unrealistic and
20 contradictory to industry accepted splicing techniques. If unloading was necessary
21 and if the Authority determined that BellSouth should recover costs for this work,
22 that work most efficiently would be performed in increments of at least 25 pairs.

1 At least 50 pairs or more would be unloaded at a time.⁴ ***BST PROPRIETARY

2 [REDACTED]

3 [REDACTED] END BST

4 PROPRIETARY*** Any experienced technician or OSP engineer understands
5 and will stress the importance of maintaining binder group integrity and
6 acknowledges that 25 pair binder groups are the very foundation of the copper
7 network.

8 **Q. ARE THERE OTHER ADVANTAGES TO CONDITIONING 50 PAIRS**
9 **PER TECHNICIAN VISIT?**

10 A. Yes, there are. Each time a technician opens a splice case in the outside plant
11 network for purposes of loading or deloading cable pairs (regardless of the
12 number of pairs loaded or deloaded), the process of opening, manipulating and
13 closing the splice case can result in significant wear and tear not only on the
14 apparatus itself, but on the contents as well. Splice cases are waterproof housings
15 that generally accommodate a significant number of spliced cables. The fewer
16 times a technician is required to open/close a splice case for purposes of loading
17 or deloading cable pairs, the less the network is degraded as a result. This is
18 especially true with pulp cable, which is insulated with paper. Deloading 50 pairs
19 per technician visit would significantly reduce the number of times a technician
20 would need to open/close any particular splice case within the network thereby
21 minimizing the negative impacts of this type of work on the network.

⁴ Because of the difficulty of singling out individual pairs, it would on average actually require less worktime to condition 50 loops at once than it would to condition 10 loops at once. For loops longer than 18,000 feet, BellSouth assumes that 2 loops will be conditioned at a time. Based upon my experience, it would take about the same length of time to condition 50 loops at once as to

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22

Q. BELLSOUTH’S COST STUDIES ASSUME THAT LARGE PERCENTAGES OF LOOP CONDITIONING JOBS WILL BE PERFORMED IN AN UNDERGROUND (MANHOLE) ENVIRONMENT. IS THAT A REASONABLE ASSUMPTION.

A. No. In response to Covad’s First Data Request Item #1, BellSouth has indicated that 47% of their load coils exist in the underground environment. However, that assumption is very misleading. First, underground structures generally exist near the central office and house the largest number of cable facilities in terms of cable pairs. These underground environments are located in the dense metropolitan areas where loop length is short. Thus, the loops are less likely to have required loading. Secondly, in a typical network, the largest percentage of customers will reside within 18,000 feet (3.4 miles) of the central offices and loading is not required on those loops. Third, since the cable pair sizes are typically much larger in the underground segment of the local network, larger capacity load coil cases were placed prior to the implementation of digital loop carrier as the preferred choice for feeder facilities. While some of these load coil cases may still be in underground plant the vast majority of the load coils within the cases will not be attached to cable pairs. For example, assume a 900 pair load coil case, (LCC) was placed in a manhole and spliced into a 2700 pair cable. When initially installed maybe all 900 load coils were spliced to cable pairs. At that point the LCC count may have been;

condition 2 loops at once.

1 824 LCC w/900 662 coils

2 Cable 1, 1-900

3 This count indicates that all load coils within the LCC are connected or spliced to
4 cable pairs.

5 However as the network was modernized and fiber fed digital loop carrier systems
6 replaced the copper feeder facilities and majority of the copper feeder facilities
7 would be re-engineered to serve distribution areas close to the central office.
8 Such re-engineering would trigger load coils removal. At that point the LCC
9 count may have changed to:

10 824 LCC w/900 662 coils

11 Cable 1, 1 – 50

12 850 coils dead

13 This count indicates that 850 load coils within the LCC are not connected or
14 spliced to cable pairs. Therefore, while a 900 pair load coil exists in the ILECs
15 records, only 5.6 % of the load coils are actually connected to cable pairs in this
16 example.

17 **Q. DOES BST REPORT THE AMOUNT OF CABLE PLANT FOR EACH**
18 **STRUCTURE TYPE BY DISTANCE?**

19 A. Yes. BST and other ILECs report the amount of cable plant by structure type and
20 length yearly to the FCC.

21 **Q. WHAT PERCENTAGE OF UNDERGROUND COPPER CABLE PLANT**
22 **WAS REPORTED BY BST?**

1 A. The following table shows the length of copper cable facilities reported to the
2 FCC by BST and United for the State of Tennessee. This indicates that only 5.3 %
3 (by distance) of BST copper cable facilities are placed within underground
4 structure and that the percentage of underground copper cable for BST is trending
5 downward as fiber fed digital loop carrier is deployed to provide feeder facilities.
6 This shows the flaw in BellSouth's assumptions about how many load points will
7 be found in underground environments. Because the underground environment is
8 the most time consuming (and costly) to work in, BellSouth's erroneous
9 assumption unnecessarily increases costs.

Outside Plant Statistics-Cable and Wire Facilities -Armis Data Table 43-08										
Source - www.fcc.gov/ccb/armis/welcome.html										
Year	Company	State	Aer Sheath Km Metallic	Aer % of Total	UG Sheath Km Metallic	UG % of Total	Bur Sheath Km Metallic	Bur % of Total	Total Aer, Bur & UG Cable Km Metallic	Total Conduit Sys Trench Km
1995	Bell South	Tennessee	50344	43.8	6535	5.7	58160	50.6	115039	2998
1996	Bell South	Tennessee	50995	43.9	6518	5.6	58669	50.5	116182	3077
1997	Bell South	Tennessee	51613	44.0	6482	5.5	59332	50.5	117427	3135
1998	Bell South	Tennessee	52537	44.1	6463	5.4	60175	50.5	119175	3174
1999	Bell South	Tennessee	53427	44.2	6457	5.3	60955	50.4	120879	3363
1995	United	Tennessee	10663	85.9	517	4.2	1239	10.0	12419	230
1996	United	Tennessee	10789	85.8	523	4.2	1268	10.1	12580	235
1997	United	Tennessee	11023	85.3	528	4.1	1365	10.6	12916	245
1998	United	Tennessee	11145	84.9	532	4.1	1443	11.0	13120	246
1999	United	Tennessee	12041	84.1	611	4.3	1666	11.6	14318	251

10

11 **Q. WHEN BST OR ANY OTHER ILEC DEPLOYS FIBER FED DLC**
12 **SYSTEMS TO REPLACE COPPER FEEDER FACILITIES SHOULD**
13 **LOAD COILS BE REMOVED IF THE "OLD" COPPER FACILITIES**

1 **ARE TO BE RE-USED WITHIN 18,000 FEET OF THE CENTRAL**
2 **OFFICE OR REMOTE TERMINAL?**

3 A. Yes. As I mentioned earlier in my testimony, any load coils on loops within
4 18,000 feet of the central office or remote terminals should be removed to ensure
5 that loading rules are not violated and engineering guidelines are followed.

6 **Q. HAS BST PROVIDED ANY EVIDENCE THAT THEY DO INDEED**
7 **REMOVE EXISTING LOAD COILS WHEN THE EXISTING COPPER**
8 **FACILITIES HAVE BEEN UPDATED WITH FIBER FED NGDLC**
9 **SYSTEMS?**

10 A. Yes. In response to Broadslate Network's Revised First Request for Production,
11 BST has produced engineering work prints that clearly demonstrate the fact that
12 BST does remove load coils as fiber fed digital loop carrier is deployed in the
13 network. ***BST PROPRIETARY [REDACTED]

14 [REDACTED]

15 [REDACTED]

16 [REDACTED]

17 [REDACTED]

18 [REDACTED]

19 [REDACTED]

20 [REDACTED]

21 [REDACTED] END PROPRIETARY ***

22 **Q. WHAT OTHER "CONDITIONING" ISSUES WERE NOTED IN**
23 **REVIEWING THIS JOB?**

1 A. Some other observations noted in reviewing this job were: ***BST

2 PROPRIETARY

3 [REDACTED]
4 [REDACTED]
5 [REDACTED]
6 [REDACTED]
7 [REDACTED]
8 [REDACTED]
9 [REDACTED]
10 [REDACTED]
11 [REDACTED]
12 [REDACTED]
13 [REDACTED]
14 [REDACTED]
15 [REDACTED]
16 [REDACTED]
17 [REDACTED]
18 [REDACTED]
19 [REDACTED]
20 [REDACTED]
21 [REDACTED]
22 [REDACTED]

23 END BST PROPRIETARY***

1 **Q. SHOULD THE AUTHORITY ACCEPT BST'S ASSUMPTION THAT**
2 **LOOPS LESS THAN 18,000 FEET WILL HAVE 2.1 LOAD COILS?**

3 A. No. This assumption and associated costs within BST's cost studies is totally
4 ridiculous. ILECs should not be entitled to charge CLECs to correct the designs
5 errors in their networks. Several other ILECs and Commissions have recognized
6 that it would be improper to require CLECs to pay for the removal of load coils
7 since these coils should have been removed over the past 20 – 30 years.

8 **Q. HAVE OTHER ILECS AND COMMISSIONS DETERMINED THAT IT**
9 **WOULD BE INAPPROPRIATE TO CHARGE FOR THE REMOVAL OF**
10 **LOAD COILS ON LOOPS LESS THAN 18,000 FEET?**

11 A. Yes. For example Bell Atlantic (Verizon) in Massachusetts has taken the position
12 that since copper loops of less than 18,000 feet should not have load coils, it
13 would remove them at its own expense. This is appropriate treatment for such
14 loops.

15 **Q. BST'S COST STUDIES ALSO ASSUME THOSE LOOPS GREATER**
16 **THAN 18,000 FEET WILL HAVE 3.5 LOADS PER LOOP. IS THIS**
17 **ASSUMPTION FLAWED AS WELL, ESPECIALLY IN A FORWARD**
18 **LOOKING NETWORK?**

19 A. Yes most definitely. Under BST's cost study assumption these loops would range
20 between 21,000 feet to 30,000 feet on average if the minimum (3000 feet) and
21 maximum (12,000 feet) end section loading rules are applied. Much different than
22 the network infrastructure design that BST witness Milner describes in his

1 testimony and I have also discussed earlier. Consequently, forward-looking
2 network design calls for the use of fiber-fed DLC systems before loops can
3 become long enough to require load coils.

4 **Q. WHAT BRIDGED TAP AND LOAD COIL GUIDELINES ARE**
5 **DICTATED UNDER THE CSA GUIDELINE, AS IT SHOULD HAVE**
6 **BEEN IMPLEMENTED FOR THE PAST 20 YEARS BY BST IN THE**
7 **STATE OF TENNESSEE?**

8 A. CSA guidelines clearly state:

9 “The maximum allowable bridged-tap is 2.5 kft, with no single bridged-
10 tap longer than 2.0 kft. All CSA loops must be unloaded.”⁵
11

12 **Q. GIVEN THE LENGTH OF TIME THAT SAC AND CSA DESIGN**
13 **GUIDELINES HAVE BEEN IN EFFECT, HOW OFTEN SHOULD IT BE**
14 **NECESSARY TO IMPOSE LOAD COIL REMOVAL AND EXCESSIVE**
15 **BRIDGED TAP REMOVAL?**

16 A. Since SAC and CSA design guidelines would have made load coil and excessive
17 bridged tap conditions obsolete over the past 20 to 30 years, almost all outside
18 plant designed prior to that is near or well past its plant life and should have been
19 replaced by now. Any instances of excessive bridge tap should be very limited or
20 non-existent. As illustrated earlier in my testimony regarding Bellcore’s “BOC
21 Notes on the LEC Networks-1994”, Issue 2, April 1994, the bridge tap on the

⁵ Bellcore, Bellcore Notes on the Networks, December 1997, p. 12-5.

1 average loop had already been reduced to 1,490 feet in 1983 and 98 % of the loop
2 were ISDN DSL capable.

3 **Q. PLEASE SUMMARIZE WHY A \$0.00 NON-RECURRING CHARGE FOR**
4 **LOOP CONDITIONING IS THE APPROPRIATE FORWARD-LOOKING**
5 **PRICE?**

6 A. Loop conditioning generally involves removing devices that were put in place in
7 accordance with embedded plant design guidelines that are long outdated. The
8 network engineering guidelines in place for the past two decades call for a loop
9 architecture that does not deploy load coils, excessive bridged taps or repeaters
10 that inhibit the provision of advanced services such as ISDN and DSL-based
11 services. The types of activities that BST has assumed for conditioning DSL-
12 capable loops only exist if one assumes a network design incorporating excessive
13 bridged taps and load coils that BST must remove to make certain loops DSL-
14 capable. That network design is fundamentally incompatible with the least-cost,
15 most efficient technology assumptions of a forward-looking economic cost study.⁶

16 Costs must be based on a forward-looking network and not on a spectrum of
17 possible networks from which BST chooses the option that produces the highest
18 cost for each specific occasion. More specifically, this Authority should not allow
19 BST to assume, for example, that its network will both have load coils and not

⁶ The TELRIC methodology assumes “the most efficient telecommunications technology currently available and the lowest cost network configuration.” Also, to comply with the FCC TELRIC methodology, a cost study may not consider costs “incurred in the past and that are recorded in the incumbent LEC’s books of accounts.” 47 C.F.R. §§ 51.505(b)(1) and (d).

1 have load coils when developing charges to impose on competitors. If BST's
 2 recurring costs are based on a network without load coils because load coils are
 3 not an efficient, forward-looking technology choice, then BST cannot reintroduce
 4 load coils to develop additional nonrecurring charges and claim that those charges
 5 are still part of TELRIC-based prices.

6 **Q. WHAT NON-RECURRING CHARGES HAS BST PROPOSED FOR**
 7 **REMOVAL OF BRIDGED TAPS AND LOAD COILS IN TENNESSEE?**

8 A. That depends upon which version of their cost study you look at. Per BST
 9 response to TRA's First Discovery Request Item #1 dated 9/8/2000 the following
 10 non recurring costs were indicated:

11	ULM	Load Coil/Equipment Removal – short	\$ 65.40
12	ULM	Load Coil/Equipment Removal – long	\$710.71
13		additional \$23.77	
14	ULM –	Bridge Tap Removal	\$ 65.44
15	U sub-loop M	2w/4w Dist Load Coil Rm	\$357.81
16		additional \$ 8.15	
17			
18	U sub-loop M	2w/4w Dist Bridge Tap Removal	\$562.71
19		additional \$ 10.19	

20
 21 The most recent cost study dated 11/09/2000 indicates the following non
 22 recurring costs:

23	ULM	Load Coil/Equipment Removal – long	\$321.99
24	ULM	Additive	\$ 12.36

1 additional \$ 12.36

2

3 I assume that the latest version is the most current and version proposed in this
4 proceeding.

5 **Q. IF THE AUTHORITY DECIDES TO PERMIT BST TO CHARGE FOR**
6 **LOAD COIL REMOVALS ON LOOPS LONGER THAN 18,000 FEET,**
7 **WHAT CHARGES WOULD BE APPROPRIATE?**

8 A. First as I have previously stated no charges should apply. However, if this
9 Authority nevertheless decides to permit BST to impose such charges then those
10 charges should be based on efficient, least-cost practices generally employed in
11 the telecommunications industry, which will be described below.

12 While a forward-looking network design results in zero conditioning charges
13 least-cost practices to determine proper loop conditioning charges which should
14 be applied in the sole event that this Authority insists on ordering conditioning
15 charges are being submitted. The tasks and work-times are based on my personal
16 experience and the experience of others familiar with performing such operations,
17 and in supervising others who performed such operations. In addition, I will be
18 prepared to perform the splicing operations before this Authority to demonstrate
19 the reasonableness of these time estimates. These times are readily achievable,
20 and the resulting rates are reasonable.

1 **Q. IF LOAD COILS MUST BE REMOVED, HOW MANY LOCATIONS ARE**
2 **NORMALLY INVOLVED?**

3 A. Once load coils are deployed, starting only when a copper loop reaches 18,000
4 feet in length, loads are immediately deployed in 6,000 foot increments, starting
5 with two or three locations (at 3,000 feet, 9,000 feet, and at 15,000 feet) with a
6 minimum of two load points. In addition, since feeder cable is normally placed in
7 conduit when close to the central office, I have conservatively assumed that the
8 first two load coil locations involve underground cable at manhole locations.
9 However it has been my experience that in a large number of locations feeder
10 cables are either on pole line structure or buried within a mile and half of the
11 office. The third location will most likely be in aerial or buried locations.
12 Therefore I have assumed that 50 percent of the time deloading of the third load
13 coil location will be at an aerial location, and 50 percent of the time at a buried
14 location. It is my opinion that the following work steps and conservative time
15 estimates can be used by this Authority to estimate the costs involved in removing
16 load coils from these three locations:

<i>Underground Cable Load Coil Removal in a Manhole</i>		
Step	Description	Task (min.)
1	Travel time to underground splice location.	20
2	Set up work area protection and underground work site.	5
3	Pump and ventilate manhole.	15
4	Buffer cable / Rerack cable / set up splice.	5
5	Open splice case.	5
6	Identify pairs to be deloaded for 1 st 25-pair binder group.	5
7	Bridge 25-pair binder group for service continuity (if necessary).	5
8	Remove / sever connection from main cable to load 'in' & 'out' taps.	3
9	Rejoin / splice 25-pair binder group through main cable.	5
10	Remove bridging modules from Step 7.	2
11	Identify pairs to be deloaded for 2 nd 25-pair binder group.	5
12	Bridge 25-pair binder group for service continuity (if necessary).	5
13	Remove / sever connection from main cable to load 'in' & 'out' taps.	3
14	Rejoin / splice 25-pair binder group through main cable.	5
15	Remove bridging modules from Step 12.	2
16	Clean, reseal, and close splice case.	10
17	Rack cables, pressure test cables in manhole.	10
18	Close down manhole, stow tools, break down work area protection.	10
Total Minutes		120
Total Hours		2.00
No. Technicians		2
Total Timesheet Hours		4.00
No. Locations		2
Total Hours		8
Pairs deloaded		50
Minutes per pair		9.6 min.

1

<i>Aerial Cable Load Coil Removal at a Pole (50% occurrence)</i>		
Step	Description	Task (min.)
1	Travel time to aerial splice location from underground splice location.	10
2	Set up work area protection.	5
3	Set up ladder or bucket truck.	10
4	Open splice case.	5
5	Identify PIC pairs to be deloaded for 1 st 25-pair binder group.	2
6	Bridge 25-pair binder group for service continuity (if necessary).	5
7	Remove / sever connection from main cable to load 'in' & 'out' taps.	3
8	Rejoin / splice 25-pair binder group through main cable.	5
9	Remove bridging modules from Step 6.	2
10	Identify pairs to be deloaded for 2 nd 25-pair binder group.	2
11	Bridge 25-pair binder group for service continuity (if necessary).	5
12	Remove / sever connection from main cable to load 'in' & 'out' taps.	3

13	Rejoin / splice 25-pair binder group through main cable.	5
14	Remove bridging modules from Step 11.	2
15	Clean, reseal, and close splice case.	10
16	Secure splice case to strand and clean up work area.	10
17	Close down aerial site, stow tools, break down work area protection.	10
Total Minutes		94
Total Hours		1.57
No. Technicians		1
Total Timesheet Hours		1.57
No. Locations		0.5
Total Hours		0.78
Pairs deloaded		50
Minutes per pair		0.94 min.

1

<i>Buried Cable Load Coil Removal at a Pedestal (50% occurrence)</i>		
Step	Description	Task (min.)
1	Travel time to buried splice location from underground splice location.	10
2	Set up traffic cone at rear bumper of truck.	1
3	Walk to site & open splice pedestal.	2
5	Identify PIC pairs to be deloaded for 1st 25-pair binder group.	2
6	Bridge 25-pair binder group for service continuity (if necessary).	5
7	Remove / sever connection from main cable to load 'in' & 'out taps.	3
8	Rejoin / splice 25-pair binder group through main cable.	5
9	Remove bridging modules from Step 6.	2
10	Identify pairs to be deloaded for 2nd 25-pair binder group.	2
11	Bridge 25-pair binder group for service continuity (if necessary).	5
12	Remove / sever connection from main cable to load 'in' & 'out taps.	3
13	Rejoin / splice 25-pair binder group through main cable.	5
14	Remove bridging modules from Step 11.	2
16	Secure splice within buried pedestal and clean up work area.	3
17	Close down buried site, stow tools and traffic cone.	5
Total Minutes		55
Total Hours		0.92
No. Technicians		1
Total Timesheet Hours		0.92
No. Locations		0.5
Total Hours		0.46
Pairs deloaded		50
Minutes per pair		0.55 min.

2

1 **Q. IF THIS AUTHORITY DECIDES TO PERMIT BST TO CHARGE FOR**
2 **BRIDGED TAP REMOVAL, WHAT CHARGES WOULD BE**
3 **APPROPRIATE?**

4 A. If this Authority elects to allow BST to impose such charges even though it
5 should not, then those costs should be based upon efficient, least-cost practices
6 generally used in the telecommunications industry. Presented below are what
7 should be considered to be reasonable costs for removing a bridged tap. The tasks
8 and work-times are based on my personal experience and others who are
9 experienced in performing such operations and in supervising others who
10 performed such operations. The task times I am proposing are readily achievable
11 and the resulting rates are reasonable.

12 **Q. IF BRIDGED TAPS MUST BE REMOVED, WHERE IN THE NETWORK**
13 **ARE THEY MOST LIKELY TO BE REMOVED, AND HOW MANY**
14 **LOCATIONS ARE NORMALLY INVOLVED?**

15 A. As explained previously, bridged taps should have been eliminated almost 30
16 years ago, except for limited end section bridged taps, which could be removed in
17 the service terminal at time of an installation visit. In addition, bridged tap should
18 not exist in underground feeder cable close to the central office. Therefore, I have
19 assumed that a single case of bridged tap, if it occurs, would occur 50 percent of
20 the time at an aerial location, and 50 percent of the time at a buried location.
21 Accordingly, it is my opinion that the following work steps and conservative time
22 estimates can be used by this Authority to estimate the costs involved:

Aerial Cable Bridged Tap Removal from Distribution at a Pole (50% occurrence)		
Step	Description	Task (min.)
1	Travel time to aerial splice location	20
2	Set up work area protection	5
3	Set up ladder or bucket truck	10
4	Open splice case	5
5	Identify PIC pairs for bridged tap removal	2
6	Remove bridging modules or cut & clear pairs	2
7	Clean, reseal, and close splice case	10
8	Secure splice case to strand and clean up work area	10
9	Close down aerial site, stow tools, break down work area protection	10
	Total Minutes	74
	Total Hours	1.23
	No. Technicians	1
	Total Timesheet Hours	1.23
	No. Locations	0.5
	Total Hours	0.62
	Pairs Unbridged	25
	Weighted Average Minutes per pair	1.48 min

1

Buried Cable Bridged Tap Removal from Distribution at a Pedestal (50% occurrence)		
Step	Description	Task (min.)
1	Travel time to buried splice location	20
2	Set up traffic cone at rear bumper of truck	1
3	Walk to site & open splice pedestal	2
4	Identify PIC pairs for bridged tap removal	2
5	Remove bridging modules or cut & clear pairs	2
6	Secure splice within buried pedestal and clean up work area	3
7	Close down buried site, stow tools and traffic cone	5
	Total Minutes	35
	Total Hours	0.58
	No. Technicians	1
	Total Timesheet Hours	0.58
	No. Locations	0.5
	Total Hours	0.29
	Pairs Unbridged	25
	Weighted Average Minutes per pair	0.70 min.

2

3

4

V. LOOP QUALIFICATION

Q. WHAT IS LOOP QUALIFICATION?

A. Loop qualification is the process of identifying the characteristics of a given loop (such as loop length and the presence and location of potential DSL-inhibiting network components such as load coils, excessive bridged taps and repeaters) and determining the suitability of that loop for provisioning DSL-based services. The characteristics of an individual loop determine whether the loop is usable for providing any type of DSL-based service, any modifications (if any) necessary to “condition” the loop to provide DSL-based service and the type/speed of DSL-based service that may be offered over that loop, with or without “conditioning.” These determinations are specific to the DSL technology and equipment that a particular carrier deploys; thus, a specific CLEC may be able to offer its DSL-based services over a loop that would not meet the incumbent’s technical specifications for DSL-based services.

The carrier-specific nature of loop qualification has significant implications for the definition of the loop qualification activity for which competitors will pay an ILEC. The ILEC can only meaningfully perform the first step of the loop qualification activity, providing access to the relevant information on loop characteristics. The CLEC’s own personnel must then use this loop characteristic information to determine the suitability of a given loop for provisioning their variants of DSL-based services.

1 **Q. HAS THE FCC AGREED THAT INCUMBENTS SHOULD PROVIDE**
2 **DIRECT ACCESS TO THE DATA THAT COMPETITORS NEED TO DO**
3 **THEIR OWN LOOP QUALIFICATION?**

4 A. Yes. The clear purpose of this FCC requirement is to require ILECs to provide
5 the information that will allow CLECs to make their own determinations about
6 whether loops are suitable to provision the technologies that the CLECs propose
7 to deploy. This purpose is implicit in the FCC's finding that "under its existing
8 rules, the relevant inquiry is not whether the retail arm of the incumbent has
9 access to the underlying loop qualification information, but rather whether such
10 information exists anywhere within the incumbent's back office and can be
11 accessed by any of the incumbent LEC's personnel."⁷ If the FCC intended for
12 BST or other ILECs to make the determination on behalf of CLECs there would
13 be no reason to require the incumbents to provide competitors with the
14 information that "back office" personnel use to perform a loop qualification
15 analysis.

16 **Q. WHERE IS THIS LOOP INFORMATION MAINTAINED BY ILECS?**

17 A. This loop makeup information is maintained in mechanized database systems by
18 ILECs. Several of the former Bell Operating Companies like BST maintain a
19 database of this loop information in the Loop Facilities Assignment and Control
20 System ("LFACS"). Cable pair information is also maintained in mechanized
21 cable plats systems that have replaced the older paper plant records or charts. BST

⁷ *UNE Remand Order* at ¶ 430.

1 utilizes a system known as Map Viewer, however there numerous other
2 mechanized CAD or similar systems are available.

3 **Q. HOW SHOULD ILECS PROVIDE THIS NECESSARY LOOP MAKEUP**
4 **INFORMATION TO CLECS?**

5 A. CLECs should receive this information through limited direct electronic access to
6 those systems and databases.

7 **Q. SHOULD THE INFORMATION THAT COMPETITORS REQUIRE BE**
8 **UBIQUITOUSLY AVAILABLE IN THE ILECS' MECHANIZED**
9 **SYSTEMS?**

10 A. Yes. Even BellSouth witness Pate admits that LFACS houses basic information
11 on 100% of loops, including length, loading, and type of facility. Pate also stated
12 that extensive detailed information was in LFACS on 80% of loops. Thus, it
13 should be possible to access data regarding the majority of loops from existing
14 legacy systems such as LFACS. It should not be necessary to develop new
15 databases or update existing databases.

16 Since these databases are used by the ILECs for loop assignment purposes, they
17 contain some loop makeup information on each and every loop. Many ILECs
18 have proactively updated their databases with current and complete cable loop
19 makeup information. This included requiring engineering work orders to provide
20 any pertinent information about changes or additions to the network so that these

1 databases would be readily updated when work was completed. In fact a few
2 years ago Bell Atlantic in the northeast area dedicated personnel specifically to
3 ensure that all loop qualification information was entered into their databases. The
4 loop makeup of all existing plant was to be entered into the database any time the
5 plant was altered. ILECs need to adhere to their own guidelines that require these
6 databases to be updated with each plant addition, change, rearrangement or
7 removal.

8 **Q. IF LOOP MAKEUP INFORMATION IS MISSING FROM THESE**
9 **MECHANIZED DATABASES AND SYSTEMS WHERE WOULD THAT**
10 **INFORMATION RESIDE?**

11 A. If the information required for loop qualification is missing from these
12 mechanized systems it would reside in the outside plant location records and work
13 prints. BST has inappropriately proposed to charge competitors for manual loop
14 qualification whenever they must resort to these outside plant location records and
15 work prints to obtain the loop makeup information because BST mechanized
16 database systems have not been properly updated and maintained. If procedures
17 and guidelines were correctly adhered to, that loop qualification information
18 would be available through databases such as LFACS.

1 **Q. WHAT WOULD YOU RECOMMEND TO THIS AUTHORITY**
2 **CONCERNING ACCESS TO LOOP MAKEUP INFORMATION?**

3 A. I would recommend that this Authority require ILECs to provide CLECs with
4 electronic access to the relevant databases for the purpose of qualifying loops for
5 xDSL-based services at the price ILECs provide such information to themselves.
6 This would be consistent with the FCC requirements that CLECs have access to
7 back office operation support systems (“OSS”) that the incumbents have access
8 to. Direct access to the databases is the efficient means to allow CLECs the
9 opportunity to qualify loops and it is also ensures that competitors and incumbents
10 have parity in terms of their ability to assess which advanced services they can
11 offer to end user customers. Information not found in these mechanized
12 databases, but available through research of an ILECs’ outside plant location
13 records should be made available without additional cost to a CLEC. In those
14 cases where the cable plant found in the OSP location records was
15 installed/rearranged after the inception of LFACS or other relevant databases, the
16 ILECs should provide the loop makeup information to the CLEC at the same
17 price as that provided via the mechanized system. Otherwise CLECs would be
18 penalized and ILECS would be rewarded for failing to follow their own
19 established record-keeping guidelines.

1 **Q. IS IT PRACTICAL FOR THE ILECS TO PROVIDE ACCESS TO THEIR**
2 **DATABASES WITH LOOP MAKEUP INFORMATION?**

3 A. Yes. It is entirely feasible for the ILECs to provide a direct read-only access to
4 LFACS and similar databases. ILEC field operations personnel have been able to
5 obtain such access for years. A forward-looking cost study for CLEC access to
6 loop makeup information should assume that the competitor has such
7 nondiscriminatory access to databases providing information relevant to loop
8 makeup. Given that access, there is no activity associated with loop qualification
9 that a competitor's own personnel could not perform on its own behalf to qualify
10 loops for xDSL services. An analysis that assumes BST will impose additional
11 costs on competitors to "qualify" loops on the competitors' behalf therefore
12 assumes that the ILEC will not comply with FCC requirements and will not
13 provide nondiscriminatory access to its OSS and related databases. If ILEC's
14 interfaces to databases interpret, exclude or restrict access to available data, they
15 will not constitute acceptable access to the appropriate access to loop qualification
16 data.

1 **Q. IF IT IS NECESSARY TO MANUALLY OBTAIN MISSING**
2 **INFORMATION THAT IS NOT AVAILABLE IN AN ILEC’S**
3 **ELECTRONIC DATABASE, HOW SHOULD A FORWARD-LOOKING**
4 **COST ANALYSIS DETERMINE THE APPROPRIATE COST TO**
5 **PROVIDE THAT INFORMATION?**

6 A. Even if a manual lookup is needed, the cost should be based on a forward-looking
7 charge for an electronic “dip” into the ILEC’s database. An incumbent’s failure
8 to keep its databases up-to-date or automate other records is not the fault of a
9 CLEC ordering a DSL-capable loop. The CLEC should also not be held
10 responsible for an incumbent’s cost to update its databases.

11 **Q. DOES THIS CONCLUDE YOUR REBUTTAL TESTIMONY?**

12 A. Yes, thank you.

DEAN R. FASSETT

Juniper Drive
Ballston Spa, New York 12020

Primary Residence: (518) 885-5461
Secondary Home: (518) 873-2080
Office: (518) 885-2840

OUTSIDE PLANT ENGINEERING/CONSTRUCTION CONSULTANT

Expert witness / consultant specializing in the engineering, construction and operation of outside plant telecommunications networks. Solid experience in the overseeing and coordinating the design and outside plant (OSP) engineering and construction responsibilities as an Operations Manager. Also, extensively experienced in OSP engineering design. An effective supervisor of technical personnel and able to manage capital programs and expense budgets within company objective levels. Skilled in coordinating / communicating with departments, major customers and government authorities.

ADIRONDACK TELCOM ASSOCIATES**Owner****1996 – Present**

Expert outside plant engineering and construction consultant/witness

- Provided outside plant local loop expert advice to AT&T and MCI for the HAI Model, a key economic model referenced by the FCC and various state jurisdictions to determine compliance with the Telecommunications Act of 1996 to set Unbundled Network Element prices and to determine the level of the Universal Service Fund.
- Appeared before 11 state jurisdictions on behalf of AT&T and MCI as an expert OSP engineering and construction witness. Testified before Public Service agencies in the states of Colorado, Idaho, Iowa, Montana, Minnesota, North Dakota, South Dakota, New Mexico, Utah, Washington and Wyoming. Assisted other expert witnesses with testimony in other jurisdictions.
- Provided field reviews of OSP facilities at selective locations in Massachusetts for USN Communications Inc.
- Engineered and designed fiber optic transmission network for a private organization in Schroon Lake, New York

FRONTIER COMMUNICATIONS OF AUSABLE VALLEY**1998 – 2000****Operations Manager/Engineer**

- Responsible for all aspects of company operations within service area
- Supervised 7 field technicians, 3 central office technicians and an office sales representative
- Responsible for the engineering, design and construction of all OSP projects, including coordination with other utilities and service providers, preparation and awarding of contractor contracts and securing of material and test equipment.
- Designed and constructed a fiber optic transmission network between central offices.
- Designed and constructed a telecommunications network to meet service requirements for Whiteface Mountain Ski Center and the first Winter Goodwill Games held in February, 2000. This network included the installation of two fiber-fed digital loop carrier systems and also fiber optic digital facilities for live TV broadcasting during the Goodwill Games. This network was designed and constructed in some very challenging terrain and has positioned the Olympic Regional Development Agency at Whiteface Mountain with one of the most advanced communications networks of any ski area in the country. This fiber optic network also extends to the very summit of Whiteface Mountain to meet the special telecommunications requirements of numerous government agencies.
- Frontier Communications of AuSable Valley received a commendation from the New York State Public Service Commission in recognition of improved customer service levels for 1999.

Contract Outside Plant Engineer and Construction Coordinator

- Designed OSP facilities to meet customer requirements for residential and business customers in the company service area.
- Coordinated and managed the construction of OSP projects, including the ordering of materials, coordination with other utilities and government agencies and administration of construction contracts.

NYNEX (NEW YORK TELEPHONE)**1970-1996****Area Construction / Engineering Operations Manager (1994-1996)**

Oversaw OSP construction and engineering operations for the Adirondack District, covering 43 wire centers and a customer base of approximately 188,000 access lines. Supervised 14 first level management and 71 craft personnel responsible for designing and building Outside Plant facilities to meet customer requirements and corporate financial commitments.

- By making sure designs, constructions schedules, purchase orders for equipment and outside plant facilities, and permits were acquired when required, put into service the SONET fiber interoffice ring system on schedule. This upgrade assures that services will not be interrupted, even with downed lines, in the Albany - Glens Falls area. Through the same oversight approach, also assured the successful design/construction of dual fiber interoffice trunk routes between nine Central Offices.
- Improved service standards throughout a large portion of the Adirondacks by overseeing timely completion of the Glens Falls Central Office switch cutover to the new #5ESS technology and a \$1.2 million municipal relocation project between Malone and Brainardsville.
- Saw the advantage of deploying fiber optic digital technology when informed by NYS of its plan to move and rebuild one of its Interstate I-87 bridges. Negotiated the change with the Department of Transportation which saved the state, federal government and the company \$500,000.

Engineering Manager - Adirondack/Capital South Districts (1990-1994)

Initially supervised the OSP Engineering Design group for the Capital South district, covering 26 wire centers with approximately 200,000 access lines with Albany and several major customers located within the district. In 1992 took over the Adirondack district's 43 wire centers and approximately 185,000 access lines serving the northern 518 area. Supervised up to ten Engineers and 12 Engineering Support (Craft) personnel in satisfying residential and business customer service requirements. Managed the Capital program and related expense budgets within established company objective levels that ranged between \$13-\$20 million to provide residential, business and interoffice trunk facilities.

- Managed a \$10.7 million project for the design and construction of a 117 mile interoffice fiber optic facility between Saranac Lake, Plattsburgh and Glens Falls which now provides SONET Ring capability to all offices North of Glens Falls in the 518 LATA. This required negotiating with New York State Departments of Environmental Conservation and Transportation, and the Adirondack Park Agency to place facilities through some of the most environmentally sensitive geography within the eastern United States. This project won the NYSDEC award for environmental excellence.
- Assigned to manage a problem Engineering Group and, by building confidence in their expertise, established a close, effective team relationship between engineering and other departments, which significantly improved work performance and service results.
- Established solid relationships between the company and such major customers as Blue Cross Blue Shield by making sure that fiber optic upgrades were designed and built to meet customer requirements.

Outside Plant Engineer - Albany/Oneonta (1979-1990)

Other than size, responsibilities the same for both districts. Designed OSP facilities that met customer requirements for residential and business service, including design of digital loop carrier systems and interoffice trunk facilities. Prepared / administered authorizations within the Capital Program. Turf assignments ranged from six to fifteen wire centers.

Construction Control Center Foreman - Oneonta (1976-1979)

Scheduled and supervised field construction operations with the Engineering department and other departments to ensure that commitments were met. Also, coordinated construction operations with other utility companies and municipalities. Maintained accurate labor time reports and material disbursement accounting.

Prior NYNEX Experience (1970-1976)

Started as a Construction Splicing Technician. Promoted to Construction Splicing Foreman, supervising up to 12 Construction Splicing Technicians in 1976.

OTHER WORK EXPERIENCE

Self Employed - Dairy Farmer (1967-1970)

Park Ranger - Central NYS Park Commission (summer 1966)

Crew Foreman - Central NYS Park Commission (1964-1965)

EDUCATION

State University of New York at Cobleskill (1965-1967)

- AAS Degree - Dairy and Food Science, 1967

- Graduated with honors

1 BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

2

3 In re: Investigation into) Docket No. 990649-TP
4 Pricing of Unbundled) Order No.
5 Network Elements.) PSC-00-1284-PHO-TP
6) Issued: July 14, 2000

5

6

7 DEPOSITION OF

8

9 MICHAEL K. ZITZMANN

10

11

12 July 20, 2000

13

14

15

16 Suite 4300
17 675 W. Peachtree Street
18 Atlanta, Georgia

19

20

21

22

23

24

25

26 Colleen B. Seidl, CCR-B-1113, RPR, CRR

27

28 BROWN REPORTING, INC.
29 1740 PEACHTREE STREET, N.W.
30 ATLANTA, GEORGIA 30309
31 (404) 876-8979

32

1 Q. Yes.

2 A. Yes.

3 Q. Are there any other documents which relate
4 to your input that you've ever seen?

5 A. In relations to this particular item, two-
6 wire ADSL compatible loop?

7 Q. Yes.

8 A. No.

9 Q. And that estimate there is 180 minutes,
10 right?

11 A. Yes.

12 Q. Where did that estimate come from?

13 A. I provided that estimate.

14 Q. What activities are involved in the 180
15 minutes?

16 A. That's handling the Service Inquiry,
17 looking up the facilities, checking the loop makeup,
18 pulling the loop makeup, inputting the loop makeup,
19 filling out the SI form, sending it back to the
20 originator.

21 Q. So that's all manual activity?

22 A. It is all manual activity.

23 Q. I'm sorry if I asked you this before.
24 Have you ever used LFACS to go find a loop?

25 A. Yes.

1 clarify it. Have you ever gone to look for an
2 unbundled copper loop in LFACS?

3 A. I have not.

4 Q. When you provided this estimate, who did
5 you talk to about looking for those in LFACS?

6 A. I think I just mentioned that you can't
7 really find them in LFACS. What you find in LFACS is
8 spare facilities. Then you've got to verify that
9 they are compatible with that particular loop type.

10 Q. Did you ever talk to anybody who worked in
11 a SAC Center and looked for unbundled copper loops
12 about how long it takes to find them?

13 A. No, because when we developed these costs,
14 they weren't yet doing them.

15 Q. On 2/2/2000 you weren't yet looking for
16 unbundled copper loops?

17 A. No, I take that back. I did not talk to
18 anyone about it.

19 Q. If LFACS has enough data in it, isn't it
20 possible that it would take five minutes to find an
21 unbundled copper loop?

22 A. No. It takes longer than five minutes to
23 log in.

24 Q. Are you presuming there's a separate log-
25 in for each inquiry in this estimate?

1 A. It was a general assumption that sometimes
2 that would have to be done.

3 Q. How many times? You don't know?

4 A. I don't know.

5 Q. So how could you include that as an
6 assumption?

7 A. It is just general in the time expectancy,
8 in the times that I provided.

9 Q. So it's just a general assumption in the
10 2.5 hours. So the 2.5 hours includes theoretical
11 research that an engineer may have to do?

12 A. Yes.

13 Q. But you don't know how often he has to do
14 that?

15 A. No.

16 Q. You don't know how much of that time that
17 2.5 hours includes that?

18 A. No.

19 Q. You've used LFACS, right?

20 A. Yes. I don't have extensive use of LFACS
21 experience, but yes. You see, when I was an
22 engineer, LFACS was brand new, and I had for a couple
23 years before I left the engineering district. So I
24 have been in it and I have been in it since, but I'm
25 not a LFACS SME, so I can't do everything that a

1 LFACS SME can do.

2 Q. But you know how long things take in
3 LFACS?

4 A. As the screen pop-ups, yes.

5 Q. I think you testified earlier that it may
6 only take five minutes to pull up a loop?

7 A. When you say pull up a loop, what you're
8 looking for is cable facilities; and yes, it could
9 take as little as five minutes.

10 Q. Could it take less than that?

11 A. I can't see how it could take less than
12 that, no.

13 Q. We talked a little bit about you logging
14 in for each entry?

15 A. Yes.

16 Q. How does that work?

17 A. You log into LFACS by wire center.

18 Q. Okay.

19 A. So you first either have to know what wire
20 center you want to go into and you put the wire
21 center code in there and then you can log into the
22 system.

23 Q. And the code is just one line entry, you
24 type it in, right? The wire center code?

25 A. Yeah, it is a three-digit identifier.

1 Q. Three-digit identifier, and your
2 engineers, they know which wire centers they are
3 responsible for, right?

4 A. Yes.

5 Q. So they know those pretty much off hand,
6 probably by memory?

7 A. Right.

8 Q. So they just type that in, three digits?

9 A. Yes.

10 Q. That's logging in?

11 A. Yeah, after you get into IMS security.
12 You have to do that first.

13 Q. Is there any reason why they wouldn't go
14 in, like I do, at the beginning of the day and log
15 in?

16 A. They probably do.

17 Q. So we don't have to consider that IMS
18 security log-in. We just are going to consider the
19 individual wire center log-in, right?

20 A. Well, what do you mean by right? I don't
21 know, maybe they don't do that. You said they could
22 and I said, yes, they could; but I don't know if they
23 specifically leave it on all day.

24 There are security issues where you're not
25 supposed to leave your terminal up and running during

1 the day if you're not at the terminal. You're
2 supposed to log off.

3 Q. Is that a BellSouth procedure?

4 A. It's supposed to be.

5 Q. So you're not supposed to leave your
6 terminal unattended even in the SAC Center?

7 A. You are supposed to lock it up. There are
8 ways to lock them up.

9 Q. Lock it up?

10 A. On a PC you can lock it.

11 Q. You can lock your screen?

12 A. Yes.

13 Q. But that wouldn't require logging out?

14 A. Right.

15 Q. Now, you are responsible for gathering the
16 inputs that tell us how long it takes to do these
17 tasks for a ADSL and UCL loop, right?

18 A. Yes.

19 Q. So when you're gathering these inputs, did
20 you or did you not consider that the engineer was
21 logging in each time for each different ADSL loop?

22 A. I didn't go down to that detail.

23 Q. You did not?

24 A. I did not.

25 Q. Did you consider the possibility that he

1 may be logging in for each time?

2 A. It was an overall general assumption that
3 that was the amount of time it would take no matter
4 what it was on average. If that included logging in,
5 it would be in there; but there's no specific item
6 for logging in, other than changing wires.

7 Q. How much time did you allocate for
8 changing wires?

9 A. There was no specific amount of time for
10 that particular subset. It's lumped into the two and
11 a half hours to get in and out of databases and do
12 the necessary terminal transactions in order to
13 preserve and find out the spare pairs that are
14 available.

15 Q. Do you know if logging out was included?

16 A. I think I just told you that I didn't go
17 down to specific details on that.

18 Q. You said making the necessary reservations
19 in LFACS is also a part of the 30-minute clerical
20 work; right?

21 A. Yes.

22 Q. How is that information conveyed back to
23 the clerical folks?

24 A. I'm not sure exactly how each district
25 does it. There are many ways. I anticipated when I

1 BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

2

3 In re: Investigation into) Docket No. 990649-TF
4 Pricing of Unbundled) Order No.
5 Network Elements.) PSC-00-1284-PHO-TF
6) Issued: July 14, 2000

5

6

DEPOSITION OF

7

JAMES FRANKLIN ENNIS

8

9

10 July 20, 2000

11 1:30 p.m.

12

13

14 Suite 4300
15 675 W. Peachtree Street
16 Atlanta, Georgia

16

17

18

19

20

21

22 Colleen B. Seidl, CCR-B-1113, RFR, CRR

23

24 BROWN REPORTING, INC.
25 1740 PEACHTREE STREET, N.W.
 ATLANTA, GEORGIA 30309
 (404) 876-8979

1 Then a person, a technician, is responsible for
2 accomplishing the tasks that we do.

3 Q. Now, are you aware of something called an
4 ADSL compatible loop?

5 A. Yes.

6 Q. If the technician receives one of those
7 and I assume that the WAPA will show you that it is
8 an ADSL compatible loop or order number something or
9 other?

10 A. Not on the work list, but there is another
11 screen in WAPA that you can determine what type of
12 loop it is.

13 Q. Now, if a technician has one of those on
14 his or her work list, what do they do with it?

15 MR. TWOMEY: Let me object to the
16 form of the question. You mean an order
17 for an unbundled ADSL loop?

18 MR. CUTLER: Yes.

19 THE WITNESS: Yes, there are certain
20 functions that are the same regardless of
21 type of service. They would do those
22 functions.

23 An ADSL capable loop has some unique
24 testing requirements, so the technician
25 would recognize the type of loop, do the

1 things that they do for all loops and then
2 also do the specialized testing required
3 for ADSL loops.

4 Q. (By Mr. Cutler) First let's talk about
5 what they do for all loops?

6 A. Okay.

7 Q. What is the next step?

8 A. I'll try to remember all of the steps.
9 The first thing that they would do is look at a work
10 list. They would assign -- there are different
11 positions in the center, so one person would do what
12 we call screening, which is a verification of the
13 design, and handle any escalations that need to be
14 done.

15 Then they would pass it over to a
16 technician that would be turning up the circuit.
17 That technician is responsible for escalations for
18 dispatch and wiring.

19 They are also responsible for testing the
20 circuit. Once the circuit has been successfully
21 installed and tested, they are responsible for
22 contacting the customer and providing that customer
23 the circuit.

24 Q. Let's start with escalations. Why would
25 there have to be an escalation when you immediately

1 got the work order?

2 A. There are not necessarily immediately when
3 you get it. All designed orders have critical dates
4 and based on the critical dates, the UNE Center
5 escalates for work to be done by that date. If the
6 work is not done by that date, the UNE Center is
7 responsible for escalating to get the work done.

8 Q. When you say all designed orders, does the
9 UNE Center also hand SL1?

10 A. Yes, they do.

11 Q. On those, those aren't designed?

12 A. They are not.

13 Q. On those, do they just -- what do they do
14 differently on SL1?

15 A. Well, there would be no verification of
16 the design, of course. There are no test points in
17 the circuit, so there would be no preinstallation
18 testing.

19 Q. What's involved in verifying the design?

20 A. In our systems a service order flows
21 through our systems and picks up assignments, which
22 is the cable and pair that the service will be
23 supplied on. That circuit then travels through the
24 design process where the CPG engineers the circuit,
25 and verification of the design entails matching up

1 those two separate things to ensure that they are the
2 same; and if there are any discrepancies, we would
3 escalate to get them to match.

4 MR. TWOMEY: Did somebody join the
5 call?

6 THE WITNESS: Yes, this is John Foms. I'm
7 sorry to come in late.

8 MR. CUTLER: I think a lot of other
9 people are emulating your example, but
10 thank you.

11 Q. (By Mr. Cutler) How can you tell just
12 sitting there whether the cable impaired match-up?

13 A. It's a stare and compare, which means you
14 have to have both screens in front of you to be able
15 to tell the difference.

16 Q. Do they each have identifying numbers or
17 something like that?

18 A. They would be, yes. Technicians are
19 trained to recognize the information.

20 Q. Is there some reason why that can't be
21 done automatically?

22 A. I couldn't tell you, I don't know.

23 Q. Now on the test points, does that involve
24 doing a remote test?

25 A. Yes.

1 A. No.

2 Q. How does that happen then?

3 A. I don't know.

4 Q. So the UNE --

5 A. Well, I hate to say that. The UNE Center

6 is responsible for verifying that a dispatch occurs,

7 okay. We don't actually do the dispatch, but we do

8 verify that a dispatch has occurred.

9 Q. I think you were talking about some kind

10 of testing being done by the UNE Center?

11 A. That's true.

12 Q. So when they do the test, though, there

13 has to be somebody at the other end of it. Weren't

14 you telling me that?

15 A. That is a product specific thing.

16 Q. And I'm intending -- and that was a bad

17 question. I'm trying -- generally speaking I'll be

18 talking about ADSL compatible loops and UCLs?

19 A. Yes.

20 Q. Let's just make it clear here. For a UCL

21 for instance, the UNE Center has to test it prior to

22 handing it over; correct?

23 A. That's correct.

24 Q. Now, presumably they have to -- either

25 somebody else dispatch somebody to be at the other

1 A. No. That would still be manual in the
2 ACAC.

3 Q. Let's turn to line 6, is that automated in
4 the ACAC?

5 A. No.

6 Q. Line 8 can obviously not be automated.
7 Where do those numbers come from?

8 A. The numbers in parenthesis?

9 Q. Yes.

10 A. Those numbers came from a sheet that the
11 cost person supplied me.

12 Q. I guess without a time and motion study
13 10.8 and 3.57 seem to be terribly precise numbers to
14 me. How did you determine whether those were
15 accurate as opposed to 11 minutes?

16 A. Those numbers were supplied to me from the
17 cost people as based on numbers that were derived in
18 the ACACs. I do not know if that was done with a
19 time and motion study or not.

20 Q. What was your response when they supplied
21 you with the numbers?

22 A. I looked at the numbers that they
23 supplied, thought back to my experience with the
24 center, and agreed that those numbers were good.

25 Q. How did you decide that it should be

1 10.8 as opposed to 11 minutes?

2 A. Well, in other words, I just agreed with
3 the numbers that they gave me. They indicated that
4 these were the numbers that were supplied by the
5 ACACs or in some way and asked me if those numbers
6 were good, and I said yes.

7 Q. Let's turn down to line or sort of number
8 16.

9 A. Okay.

10 Q. Do you agree with the 10 percent number
11 for reuse for ISDN and ADSL?

12 A. Do I agree with it?

13 Q. Yeah.

14 MR. TWOMEY: Line 12 or 15?

15 MR. CUTLER: 16.

16 MR. TWOMEY: I'm sorry, okay, 16.

17 THE WITNESS: Yes, I do agree.

18 Q. (By Mr. Cutler) Why is 10 percent the
19 right number?

20 A. The 10 percent number was based on some
21 data gathered by the cost people and supplied to me.
22 After listening to their explanation of the numbers,
23 I agreed with them that it was valid.

24 Q. Do you see that data anywhere in this POD?

25 A. No, I do not.

1 I did not supply any of the percentages.
2 I strictly gave work times and the cost people came
3 up with the percentages.

4 Q. Based on your experience working in the
5 UNE Center, does 10 percent seem like the right
6 amount of time that circuits are reused?

7 A. No.

8 Q. What seems like the right number?

9 A. Zero percent.

10 Q. Nobody orders ADSL compatible loops to be
11 put -- to be a substitute for a voice line?

12 A. No, they do not. Not currently.

13 Q. How about ISDN?

14 A. I have not seen any ISDN conversion
15 orders. Conversion orders would mean reuse of
16 facilities.

17 Q. Let's turn to the one which says, which is
18 titled Unbundled Loop ACAC Cost. Have you ever seen
19 this document before?

20 A. Yes.

21 Q. Is this a document you were referring to
22 with the ACAC data?

23 A. Yes.

24 Q. Do you have any idea where this data came
25 from?

1 BEFORE THE FLORIDA PUBLIC SERVICE COMMISSION

2
3 In re: Investigation into) Docket No. 990649-TP
4 Pricing of Unbundled) Order No.
5 Network Elements.) PSC-00-1284-PHO-TP
6) Issued: July 14, 2000

7 DEPOSITION OF

8 DANIEL ERIC STINSON

9
10 July 20, 2000

11 3:55 p.m.

12
13 Suite 4300
14 675 W. Peachtree Street
15 Atlanta, Georgia

16
17
18
19
20
21
22 Colleen B. Seidl, CCR-B-1113, RPR, CRR

23 BROWN REPORTING, INC.
24 1740 PEACHTREE STREET, N.W.
25 ATLANTA, GEORGIA 30309
 (404) 876-8979

1 MR. CUTLER: 64.

2 MR. TWOMEY: We may be on the wrong
3 sheet. There appear to be two note 5's.

4 MR. CUTLER: There are, but the one
5 on line 64 is the one I'm interested in.

6 MR. TWOMEY: Which says -- read what
7 it says before you answer the question so
8 there's no confusion.

9 THE WITNESS: Me, COI&M field, connect to
10 test, assumes 15 percent of total COI&M
11 filled time carried in other transport
12 elements.

13 The question one more time.

14 Q. (By Mr. Cutler) What is your
15 understanding of the meaning of that note?

16 A. The meaning of that note is that 15
17 percent of the total time given would be charged
18 through another element.

19 Q. Such as?

20 A. Co-location cross connect element.

21 Q. Which is another nonrecurring charge?

22 A. I do not know that.

23 MR. CUTLER: Let's run through quickly
24 some of these other areas.

25 MR. TWOMEY: Are you finished with

1 you rephrase it for me?

2 Q. Yes. Excuse me. I got the wrong numbers.
3 Of the 20-minute estimate for the first install, the
4 division of time between looking things up and
5 walking around and actually wiring is 8 minutes to do
6 the actual wiring and 12 minutes to look up the work
7 order and walk from the TIRKS machine, presumably I
8 guess the WAFA, to where you're going to do it?

9 A. I still don't follow you. I don't find
10 the 8 minutes.

11 Q. Let's go back through that one more time.
12 I'll try to be less obtuse in my questioning.

13 What I'm trying to figure out is, how much
14 time is involved in each one of the activities to run
15 these jumpers? In other words, how much time is
16 spent looking it up in WAFA? How much time is spent
17 walking from the computer terminal to the frame?
18 That kind of stuff.

19 My question is, based on the fact that the
20 first install is 20 minutes and the second one is
21 8 --

22 MR. TWOMEY: I think that's where the
23 witness is having troubles.

24 MR. CUTLER: Maybe that's our problem.

25 Q. (By Mr. Cutler) Then I'm looking at

1 the wrong document. It is ten minutes. I apologize.

2 A. Okay, correct.

3 Q. Amending that question to say, is it fair
4 to say ten minutes is the time involved in looking
5 things up and walking around?

6 MR. TWOMEY: Just to be precise, that
7 question is 10 minutes of the 20 under
8 first, looking things up and walking
9 around.

10 MR. CUTLER: Yes.

11 MR. TWOMEY: Do you understand the
12 question?

13 THE WITNESS: Yes, I do. And the answer
14 is yes, sir.

15 MR. CUTLER: All right. Since we have
16 five minutes left, I'm going to page a few
17 interrogatories, but if someone else would
18 like to ask a question on the phone feel
19 free.

20 MR. TWOMEY: Just to give you the
21 appropriate incentives, as it stands now I
22 have no questions.

23 MR. CUTLER: You can ask one now.

24 FEMALE VOICE: Could I confirm this
25 is the same court reporter as the previous

CERTIFICATE OF SERVICE

I hereby certify that a true and correct copy of the foregoing has been forwarded via U.S. Mail, postage prepaid, and/or hand delivered to the following on this the 20th day of November, 2000.

Guy Hicks, Esq.
BellSouth Telecommunications, Inc.
Suite 2101
333 Commerce Street
Nashville, Tennessee 37201-3300

Jim Lamoureux
AT&T
1200 Peachtree St., NE
Room 4060
Atlanta, GA 30309

Jon Hastings, Esq.
Boult, Cummings, Conners & Berry PLC
414 Union St., Suite 1600
Nashville, TN 37219

James Wright, Esq.
United Telephone Southeast
14111 Capitol Blvd.
Wake Forest, NC 27587

Charles B. Welch, Esq.
Farris, Mathews, Branran & Hellen PLC
205 Capitol Blvd., Suite 303
Nashville, TN 37219

R. Dale Grimes, Esq.
Bass, Berry & Sims, LC
2700 First American Center
Nashville, TN 37238-2700

Dana Shaffer, Esq.
NEXTLINK Tennessee, Inc.
105 Molloy St., Suite 300
Nashville, TN 37201

Michael Bressman, Esq.
BlueStar Networks, Inc.
Five CorporateCentre Dr., Suite 600
Franklin, TN 37067

Catherine F. Boone, Esq.
COVAD Communications, Inc.
10 Glenlake Parkway, Suite 650
Atlanta, GA 30328


Clay Arendes, Esq.
Vectris Telecom, Inc.
6500 River Place Blvd.
Building 2, Suite 200
Austin, TX 78730

Eric J. Branfman, Esq.
Marc B. Rothschild, Esq.
Swidler, Berlin, Shereff, Friedman, LLP
3000 K Street, Suite 300
Washington, DC 20007-5116

Susan Berlin, Esq.
MCI Telecommunications d/b/a
MCI WorldCom
6 Concourse Parkway
Atlanta, GA 30328

Bennett Ross, Esq.
BellSouth Telecommunications, Inc.
675 W. Peachtree St., Suite 4300
Atlanta, GA 30375

John Spilman
Director of Regulatory Affairs and
Industry Relations
BroadSlate Networks, Inc.
675 Peter Jefferson Parkway, Suite 310
Charlottesville, VA 22911


Henry Walker